


AD-A103 935

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON --ETC F/G 13/13
NATIONAL DAM SAFETY PROGRAM, MAPLE LAKE DAM (NJ 00776), PASSAIC--ETC(U)
JUL 81 W GUINAN DACW61-79-C-0011

UNCLASSIFIED

DAEN/NAP-53842/NJ00776-81/ NL

1 OF 2
ADA
103935



LEVEL II

1

AD A103935

PASSAIC RIVER BASIN
GOFFLE BROOK, BERGEN COUNTY
NEW JERSEY

MAPLE LAKE DAM NJ 00776

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED.

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

DTIC
ELECT
SEP 9 1981

JULY 1981

D

REPT. NO. DAENINAP-53842/NJ 00776-81/07

81 9 09 040

FILE COPY

(10) W. 1000 / 61

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER DAEN/NAP-53842/NJ00776-81/07	2. GOVT ACCESSION NO. AD-A103935	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program. Maple Lake Dam (NJ00776) Bergen County, New Jersey		5. TYPE OF REPORT & PERIOD COVERED 9) FINAL report
7. AUTHOR(s) Guinan, Warren, P.E.		6. PERFORMING ORG. REPORT NUMBER 15
9. PERFORMING ORGANIZATION NAME AND ADDRESS Anderson-Nichols 150 Causeway St. Boston, MA 02114		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 11
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection Division of Water Resources P.O. Box CN029 Trenton, NJ 08625		12. REPORT DATE July 1981
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106		13. NUMBER OF PAGES 50
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		15. SECURITY CLASS. (of this report) Unclassified
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams Embankments Visual Inspection Structural Analysis National Dam Safety Program Maple Lake Dam, N.J. Spillways Erosion		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		



IN REPLY REFER TO

NAPEN-N

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT CORPS OF ENGINEERS
CUSTOM HOUSE - 2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

31 AUG 1981

Accession For		
NTIS	GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB		<input type="checkbox"/>
Unannounced		<input type="checkbox"/>
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or	Special
A		

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Maple Lake Dam in Bergen County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Maple Lake Dam, a high hazard potential structure, is judged to be in poor overall condition. The dam's spillway is considered inadequate because a flow equivalent to 21 percent of the Spillway Design Flood - SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood.) The decision to consider the spillway "inadequate" instead of "seriously inadequate" is based on the determination that dam failure resulting from overtopping would not significantly increase the hazard to loss of life downstream from the dam from that which would exist just before overtopping failure. To ensure adequacy of the structure, the following actions, as a minimum are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. Within 30 days from the date of approval of this report the owner should engage a qualified professional consultant to design and oversee procedures for the removal of trees, vines, and brush from the upstream and downstream slopes and for a distance of 25 feet from the downstream toe of the dam or limits of property, whichever is less.

c. Within six months from the date of approval of this report the owner should engage a qualified professional consultant to perform the following:

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

NAPEN-N

Honorable Brendan T. Byrne

(1) Design and oversee repairs for the eroded areas on the downstream slope adjacent to the spillway, along the toe, and at the footpaths near the steel grating stairway.

(2) Design necessary remedial measures to prevent erosion of the toe by water flowing in the discharge channel downstream from the spillway.

(3) Design or specify repairs for the erosion of the upstream slope of the dam and design and specify erosion protection for the upstream slope of the dam.

(4) Investigate the cause of the wet, soft area 20 feet downstream from the toe of the dam near the left bank of the spillway channel.

(5) Design or specify reconstruction of the spillway and abutment walls.

(6) Design or specify repairs to the low level outlet.

(7) Design and oversee repairs to the cracked concrete core walls and upstream concrete walls.

d. Within three months from the date of approval of this report, the following remedial actions should be initiated:

(1) Start a program of checking the condition of the dam periodically and monitoring the wet area downstream from the toe of the downstream slope.

(2) Clear trees and brush from the discharge channel and from a zone 25 feet on either side of the discharge channel or to the property line, whichever is the lesser distance, from the spillway stilling basin to the next pond downstream.

(3) Control trespassing the dam.

(4) Start a program for maintaining the embankment free of weeds, brush, vines, and trees.

e. Within six months from the date of approval of this report the following remedial actions should be initiated:

(1) Backfill animal burrows with properly selected materials.

(2) Repair steel stairs on downstream face of dam.

f. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam, within one year from the date of approval of this report.

NAPEN-N

Honorable Brendan T. Byrne

g. An emergency action plan and warning system should be developed which outlines actions to be taken by the owner to minimize the downstream effects of an emergency at the dam within six months from the date of approval of this report.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congresswoman Roukema of the Seventh District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



ROGER L. BALDWIN
Lieutenant Colonel, Corps of Engineers
Commander and District Engineer

Incl
As stated

Copies furnished:

Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

MAPLE LAKE DAM (NJ00776)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 23 April 1981, by Anderson-Nichols and Co. Inc., under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Maple Lake Dam, a high hazard potential structure, is judged to be in poor overall condition. The dam's spillway is considered inadequate because a flow equivalent to 21 percent of the Spillway Design Flood - SDF - would cause the dam to be overtopped.. (The SDF, in this instance, is one half of the Probable Maximum Flood.) The decision to consider the spillway "inadequate" instead of "seriously inadequate" is based on the determination that dam failure resulting from overtopping would not significantly increase the hazard to loss of life downstream from the dam from that which would exist just before overtopping failure. To ensure adequacy of the structure, the following actions, as a minimum are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. Within 30 days from the date of approval of this report the owner should engage a qualified professional consultant to design and oversee procedures for the removal of trees, vines, and brush from the upstream and downstream slopes and for a distance of 25 feet from the downstream toe of the dam or limits of property, whichever is less.

c. Within six months from the date of approval of this report the owner should engage a qualified professional consultant to perform the following:

(1) Design and oversee repairs for the eroded areas on the downstream slope adjacent to the spillway, along the toe, and at the footpaths near the steel grating stairway.

(2) Design necessary remedial measures to prevent erosion of the toe by water flowing in the discharge channel downstream from the spillway.

(3) Design or specify repairs for the erosion of the upstream slope of the dam and design and specify erosion protection for the upstream slope of the dam.

(4) Investigate the cause of the wet, soft area 20 feet downstream from the toe of the dam near the left bank of the spillway channel.

(5) Design or specify reconstruction of the spillway and abutment walls.

(6) Design or specify repairs to the low level outlet.

(7) Design and oversee repairs to the cracked concrete core walls and upstream concrete walls.

d. Within three months from the date of approval of this report, the following remedial actions should be initiated:

(1) Start a program of checking the condition of the dam periodically and monitoring the wet area downstream from the toe of the downstream slope.

(2) Clear trees and brush from the discharge channel and from a zone 25 feet on either side of the discharge channel or to the property line, whichever is the lesser distance, from the spillway stilling basin to the next pond downstream.

(3) Control trespassing the dam.

(4) Start a program for maintaining the embankment free of weeds, brush, vines, and trees.

e. Within six months from the date of approval of this report the following remedial actions should be initiated:

(1) Backfill animal burrows with properly selected materials.

(2) Repair steel stairs on downstream face of dam.

f. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam, within one year from the date of approval of this report.

g. An emergency action plan and warning system should be developed which outlines actions to be taken by the owner to minimize the downstream effects of an emergency at the dam within six months from the date of approval of this report.

APPROVED:



ROGER L. BALDWIN
Lieutenant Colonel, Corps of Engineers
Commander and District Engineer

DATE:

31 Aug 31

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	Maple Lake
Identification No.:	Fed ID No. NJ00776
State Located:	New Jersey
County Located:	Bergen
Stream:	Goffle Brook
River Basin:	Passaic
Date of Inspection:	April 23, 1981

ASSESSMENT OF GENERAL CONDITIONS

Maple Lake Dam is an earthfill and concrete dam, possibly 80 years old but extensively rebuilt in 1947, that is in poor overall condition. It is small in size and should retain its high hazard classification. Trees, brush and vines are growing on the dam's earthen slopes making visual inspection difficult. Erosion has occurred on the upstream slope between the core wall and reservoir level. Erosion gullies varying in width up to 3 feet and ranging from 4 to 8 inches deep have developed at many locations on the downstream slope. Some animal burrows were found on the downstream slope. Several transverse hairline cracks were found in the concrete apron and 2-foot thick core-wall on the right side of the dam. Four transverse cracks, one badly spalled and eroded, were noted on the left side core-wall. Spalling and cracking of the spillway abutments was noted, and a major vertical crack about 2 inches deep was observed in the downstream face of the concrete spillway. The low-level pipe has several large boulders covering its outlet. The valve box for the pipe is submerged and does not appear to have been operated for a long time. Debris and boulders have accumulated in the stilling basin and discharge channel. The downstream channel has trees growing on the eroded banks. Another very low dam about 200 feet downstream ponds water up to the stilling basin intermittently. Only one area about 20 feet downstream of the toe to the left of the spillway channel was found to be wet and soft. The spillway will pass about 20 percent of the one-half Probable Maximum Flood and is considered inadequate.

We recommend that the owner retain the services of a professional engineer, qualified in the design and inspection of dams, to accomplish the following immediately: Design and oversee procedures for the removal of trees, vines, and brush from the upstream and downstream slopes and for a distance of 25 feet from the downstream toe of the dam or limits of property whichever is less; soon: design and oversee repairs for the eroded areas on the downstream slope adjacent to the spillways along the toe, and at the footpaths near the steel grating stair; design necessary remedial measures to prevent erosion of the toe by water flowing in the discharge channel downstream from the spillway; design or specify repairs for the erosion of the upstream slope of the dam and design and specify erosion protection for the upstream slope of the dam; investigate the cause of the

wet, soft area 20 feet downstream from the toe of the dam near the left bank of the spillway channel; design or specify reconstruction of the spillway and abutment walls; design or specify repairs to the low-level outlet; and design and oversee repairs to the cracked concrete corewalls and upstream concrete walls. In the near future: Perform a more detailed hydrologic/hydraulic evaluation of the inadequacy of the spillway and design and implement necessary remedial measures; and backfill animal burrows.

We also recommend that, as part of operating and maintenance procedures, the owner should accomplish the following in the time periods specified: Starting very soon: Begin a program of checking the condition of the dam periodically and monitoring the wet area downstream from the toe of the downstream slope; clear trees and brush from the discharge channel and from a zone 25 feet on either side of the discharge channel or to the property line, whichever is the lesser distance, from the spillway stilling basin to the next pond downstream; control trespassing on dam; and start a program for maintaining the embankment free of weeds, brush, vines, and trees. Starting soon: Develop an emergency action plan which outlines actions taken by the owner to minimize downstream effects of an emergency at the dam; and repair steel stairs on downstream face of dam. In the near future: Develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

ANDERSON-NICHOLS & COMPANY, INC.



Warren A. Guinan, P.E.
Project Manager
New Jersey 16848



OVERVIEW PHOTO

CAPITOL HILL

February 17, 1961

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonable possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

CONTENTS

PHASE I INSPECTION REPORT MAPLE LAKE DAM SAFETY REPORT

MAPLE LAKE DAM FED ID NO. NJ00776

SECTION		<u>Page</u>
SECTION 1	PROJECT INFORMATION	
	1.1 <u>General</u>	1
	1.2 <u>Project Description</u>	1
	1.3 <u>Pertinent Data</u>	3
SECTION 2	ENGINEERING DATA	
	2.1 <u>Design</u>	6
	2.2 <u>Construction</u>	6
	2.3 <u>Operation</u>	6
	2.4 <u>Evaluation</u>	6
SECTION 3	VISUAL INSPECTION	7
SECTION 4	OPERATIONAL PROCEDURES	
	4.1 <u>Procedures</u>	9
	4.2 <u>Maintenance of Dam</u>	9
	4.3 <u>Maintenance of Operating Facilities</u>	9
	4.4 <u>Warning System</u>	9
	4.5 <u>Evaluation of Operational Adequacy</u>	9
SECTION 5	HYDRAULIC/HYDROLOGIC	10
SECTION 6	STRUCTURAL STABILITY	12
SECTION 7	ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES	
	7.1 <u>Assessment</u>	14
	7.2 <u>Recommendations/Remedial Measures</u>	14
FIGURES	1. Essential Project Features	
	2. Regional Vicinity Map	
APPENDICES	1. Engineering and Experience Data	
	2. Check List Visual Inspection	
	3. Photographs	
	4. Hydrologic Computations	
	5. HEC1 Output	
	6. References	

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY INSPECTION PROGRAM
MAPLE LAKE DAM
FED ID NO. #NJ00776

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Authority to perform the Phase I Safety Inspection of Maple Lake Dam was received from the State of New Jersey, Department of Environmental Protection, Division of Water Resources by letter dated 12 December 1980 under Basic Contract No. FPM-39 and Contract No. A01093 dated 10 October 1979. This Authority was given pursuant to the National Dam Inspection Act, Public Law 92-367 and by agreement between the State and the U.S. Army Engineers District, Philadelphia. The inspection discussed herein was performed by Anderson-Nichols & Company, Inc.

b. Purpose: The purpose of the Phase I Investigation is to develop an assessment of the general conditions with respect to the safety of Maple Lake Dam and appurtenances. Conclusions are based upon available data and visual inspection. The results of this study were used to determine any need for emergency measures and to conclude if additional studies, investigations, and analyses are necessary and warranted.

1.2 Project Description

a. Description of Dam and Appurtenances. Maple Lake Dam is an earth fill and concrete dam, with a hydraulic height of 13.9 feet, a structural height of 14.5 feet and a length of 290 feet. The dam has a concrete core wall that is visible the entire length of the dam. The dam crest is grass-covered and has an average width of 15 feet. On the right side of the dam, approximately 12.5 feet from the upstream face lies the center line of either a 3-foot wide concrete sidewalk or another concrete core wall which extends approximately 37 feet. The upstream side of the dam crest has, on both sides of the spillway, concrete platforms used for recreation. Beyond the concrete platforms on both the right and left of the upstream side are earthen embankments. The upstream face of the dam is vertical concrete. The downstream face is a 2H:1V sloped, earthen embankment. The concrete spillway is 48 feet long, located approximately 91 feet from the road on the right

overbank. The spillway crest is flat, 2.4 feet wide, with the upstream face vertical and the downstream face sloped 2H:3V. The stilling basin at the toe of the spillway is approximately 38 feet long, 20 feet wide, and has a 2-foot end wall with a 3-foot wide overflow weir. The low-level outlet, probably a 12-inch pipe, leads from a valve box at the left upstream end of the spillway, through the dam, and along the left end of the stilling basin. The pipe is encased in concrete downstream of the spillway.

b. Location. Maple Lake Dam is located on Goffle Brook in Wycoff Township, Bergen County, New Jersey. The dam is at 40° 59.9' north latitude 74° 09.6' west longitude on the Paterson Quadrangle. A location map has been included as Figure 2. It may be reached by driving on Newton Road northward from U.S. Route 202 to the railroad station in Wortendyke; the dam is about 100 yards west of the station just south of the railroad track.

c. Size Classification. Maple Lake Dam is classified as being small in size on the basis of storage at the dam crest of 57.5 acre-feet, which is less than 1000 acre-feet but more than 50 acre-feet, and on the basis of its structural height of 14.5 feet, which is less than 40 feet, in accordance with criteria given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Visual inspection of the area below Maple Lake Dam revealed a single house just upstream of Newton Road, approximately 1300 feet downstream of the dam. Analyses indicated that up to 1.5 feet of water could flood the first floor of the house. The house is of frame construction and would probably be destroyed, thus endangering the lives of the six occupants. Newton Road, at the same elevation as the first floor of the house, would also suffer some property damage from the 1.5 feet of water. For these reasons the dam is given a High Hazard classification.

e. Ownership. The dam is owned by the Canterbury Development Corporation. The corporate officers may be reached by writing to Mr. Morris Sarna, 2375 Hudson Terrace, Fort Lee, New Jersey 07024.

f. Purpose. Maple Lake Dam was rebuilt for recreational use. Its original purpose is not known.

g. Design and Construction History. Plan #419, dated March 27, 1947 of "Existing Conditions After Repairs and New Construction," done by Frank D. Livermore, Engineer, are on file at the New Jersey Department of Environmental Protection, Prospect Street, Trenton, New Jersey 08625.

h. Normal Operational Procedure. No operational procedures were found for the dam.

i. Site Geology. No site specific geologic information (such as borings) was available at the time the dam was inspected. Information derived from the Geologic Map of New Jersey (Kummel and Johnson, 1912) and the Glacial Drift of New Jersey (Salisbury, Kummel, Peet and Whitson, 1902) indicates soils within the immediate site consist of stratified drift which may be comprised of sand and gravel plains, deltas, eskers, kames, and terraces.

No bedrock outcrops were observed during the dam inspection. The previously mentioned geologic map indicates that bedrock in this area consists of soft red shale and sandstone of Triassic age.

1.3 Pertinent Data

a. Drainage Area

2.21 square miles

b. Discharge at Damsite (cfs)

Maximum flood at damsite - unknown.

Total ungated spillway capacity at maximum pool (top of dam) elevation - 771

c. Elevation (ft. above NGVD)

Top of dam - 287.9

Maximum pool test flood surcharge - 289.3

Recreation pool (at time of inspection) - 285

Spillway crest - 285

Streambed at centerline of principal spillway - 274

Maximum tailwater (estimated) - 278

d. Reservoir (Length in feet)

Maximum pool - 800 (estimated)

Spillway crest - 700

e. Storage (acre-feet)

Spillway crest - 38.4

Top of dam - 57.5

Test flood - 75

f. Reservoir Surface (acres)

Top of dam - 9.6

Spillway crest - 6.4

g. Dam

Type - earthfill and concrete

Length - 290 feet

Height - 13.9 feet (hydraulic)

- 14.5 feet (structural)

Top width - 15 feet

Side slopes - upstream vertical, downstream 2H:1V

Zoning - unknown

Impervious core - concrete

Cutoff - unknown

Grout curtain - unknown

h. Spillway

Type - Broad crested, concrete

Length of weir - 48 feet

Crest elevation - 285 feet NGVD

Low level outlet - 12 inch pipe (estimated size)

U/S channel - Maple Lake

D/S channel - Goffle Brook

i. Regulating Outlets

Type - 1 foot x 2.5 foot concrete box encasing a
12-inch pipe

Length - 40 feet (estimated)

Access - valve box at upstream left end of spillway

SECTION 2 ENGINEERING DATA

2.1 Design

No hydraulic, hydrologic, or other design engineering data were disclosed. The design plans dated 1947 on file at NJDEP were in basic agreement with what was observed in the field. The dam plans from NJDEP did not show the low level outlet that was observed.

2.2 Construction

No recorded data concerning construction of the Maple Lake Dam were disclosed. The plans on file with NJDEP are plans detailing improvements made in 1947.

2.3 Operation

No data pertaining to the operation of the dam were found.

2.4 Evaluation

a. Availability. A search of the New Jersey Department of Environmental Protection files, and contact with community officials revealed a limited amount of information. All disclosed information with a copy of the plans was retrieved.

b. Adequacy. The plans, supplemented by visual inspection, are deemed adequate to complete this inspection.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. Dam. Trees are growing on the crest and upstream slope of the dam to the left of the spillway, on the downstream slope, and in the area at the downstream toe of the dam. The extensive vegetation on the downstream slope made it difficult to investigate the slopes thoroughly during the site visit.

The crest of the dam to the right of the spillway is comprised of a concrete apron, a 2-foot wide concrete core wall and zone of sandy soil which is partially covered with grass and vines. A 3-foot wide concrete wall was uncovered to the right of the spillway at the downstream edge of the crest which may be the top surface of another core wall. Several clusters of trees were growing near the waterline to the left of the upstream concrete apron on the left side of the dam. Erosion had occurred on the upstream slope between the core wall and reservoir level.

Erosion gullies varying in width up to 3 feet and 4 to 8 inches deep have developed at many locations on the downstream slope. Several paths are located near the steel grating stairway on the left side of the dam.

Several transverse hairline cracks were observed in the concrete apron and 2-foot thick core wall on right side. Four transverse cracks, one badly spalled and eroded, were visible on the concrete core wall, left of the spillway.

Large boulders up to 2 to 3 feet in diameter were incorporated into the lower half of slope to the right of the spillway wingwall. The boulders were partially obscured by the extensive vine growth on the slope. The area along the downstream toe exhibited no evidence of being wet and soft except for one area approximately 20 feet downstream from the toe near the left side of the spillway channel. A zone of erosion approximately 20 feet wide has occurred along the toe of the dam to the left of the spillway channel. Many boulders have been placed adjacent to the toe along this zone.

Some animal burrows and numerous small erosion gullies were observed on the downstream slope.

Another zone of small boulders was observed adjacent to the downstream toe in the vicinity of the left abutment.

b. Appurtenant Structures.

1. Ungated Spillway. The 48-foot wide concrete spillway near the center of the dam is badly spalled and eroded. One major vertical crack, up to 2 inches wide and approximately 2 inches deep, was observed on the downstream face. However, this crack shows no evidence of seepage. Both abutment walls to the spillway are badly eroded and undermined, where the abutments are in contact with the water. The right concrete spillway abutment wall has a vertical crack in the vicinity of the downstream edge of the crest, which is indicative of settlement or differential movement.
2. Gated Outlet. The downstream end of the low level outlet is badly spalled and covered with debris. The submerged valve chamber is visible on the upstream face but the valve size and condition could not be determined at the time of inspection; the operating hand wheel was missing. (Valve estimated to be 12 inches).

The entrance to the ungated spillway was generally clear of obstructions. Debris and boulders were observed on the floor of the discharge channel, both adjacent to the spillway in the stilling basin and downstream in the adjacent pond. Several boulders have been displaced from the masonry stone walls at the ends of the concrete spillway wingwalls along both sides of the spillway.

c. Reservoir Area. The watershed above the lake is gently to moderately sloping and wooded. A public beach exists along a portion of the left side of the reservoir. Slopes on the shore of the lake appear stable. No evidence of significant sedimentation was observed.

d. Downstream Channel. Erosion has occurred on the right and left banks of the channel immediately downstream of the channel for a distance of 50 to 100 feet. Trees are growing on the banks of the channel downstream of the spillway. Another low dam is located downstream which is ponding water adjacent to the stilling basin.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedures

No formal operating procedures were disclosed.

4.2 Maintenance of Dam

No formal maintenance procedures for the dam were found, but from its condition, it is apparent that maintenance is needed to prevent serious deterioration of the structure.

4.3 Maintenance of Operating Facility

No formal maintenance procedures for the operating facilities were disclosed. From the condition of the gate valve stem, it appeared that little maintenance had been done.

4.4 Warning System

No description of any warning system was disclosed.

4.5 Evaluation of Operational Adequacy

Because of the lack of operation and maintenance procedures, the remedial measures described in Section 7.2 should be implemented as prescribed.

SECTION 5
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. Design Data. Because no hydrologic or hydraulic data were revealed an evaluation could not be performed.

b. Experience Data. No experience data were found.

c. Visual Observation. The visual inspection revealed that the concrete spillway has a major vertical crack up to 2 inches deep in the downstream face. The spillway abutment walls are eroded and spalled. Some of the stone masonry in the wing walls has fallen. The stilling basin has an accumulation of large stones and debris in it. The valve box for the low-level outlet is of the submerged type on the upstream left end of the spillway. Only the valve stem was observable in the valve box. The pipe and valve are estimated to be 12-inch. The pipe is encased in concrete that measures about 2.5 feet wide by 1 foot deep and the outlet end was essentially blocked by large stones so that the actual size of the pipe could not be determined. The valve stem did not appear to have been operated recently.

d. Maple Lake Overtopping Potential. The hydraulic/hydrologic evaluation for the dam is based on a selected Spillway Design Flood (SDF) equal to one-half the Probable Maximum Flood (PMF) in accordance with the range of test floods given in the evaluation guidelines, for dams classified as high hazard and small in size. The PMF was determined by application of a 24-hour Probable Maximum Storm of 22 inches to the SCS dimensionless unit hydrograph. Hydrologic computations are given in Appendix 4. The routed half-PMF peak discharge for the subject drainage area is 3501 cfs.

The minimum elevation of the dam allows 2.9 feet of depth above the spillway, before overtopping occurs. Under this head the total spillway capacity is 711 cfs, which is less than the selected SDF (approximately 20 percent).

Flood routing calculations indicate that Maple Lake Dam will be overtopped for 6.3 hours to a maximum depth of 2.1 feet under half-PMF conditions. It is estimated that the spillway can pass about 20 percent of the half-PMF without overtopping the dam; thus, the spillway is considered inadequate.

Because of the poor condition of the dam and the High Hazard classification based on visual inspection, a breach analysis was performed to assess the increase in downstream hazard under dam failure conditions. The results of the breach analysis, for the one-half PMF test flood contained in Appendix 5, show that the downstream hazard is not worsened under dam failure conditions.

Under one-quarter PMF conditions, failure of the dam increases the flood stage by 2.2 feet at the damage center. However, it is unlikely that the dam would fail from a one-quarter PMF discharge, which creates 4.3 hours of overtopping to a maximum depth of 0.6 foot.

Because of the poor condition of the dam and the High Hazard classification based on visual inspection, a breach analysis was performed to assess the increase in downstream hazard under dam failure conditions. The results of the breach analysis, for the one-half PMF test flood contained in Appendix 5, show that the downstream hazard is not worsened under dam failure conditions.

Under one-quarter PMF conditions, failure of the dam increases the flood stage by 2.2 feet at the damage center. However, it is unlikely that the dam would fail from a one-quarter PMF discharge, which creates 4.3 hours of overtopping to a maximum depth of 0.6 foot.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability. The presence of a dense growth of trees, brush and vines on the downstream slope, and grass, vines and coarse weed at the downstream edge of the crest makes it impossible to make an adequate visual inspection of the embankment.

Trees growing on the upstream and downstream slopes of the embankment and in the area immediately downstream of the toe may blow over and pull out their roots or they may die with the result that their roots rot. In either case, serious seepage and erosion problems could result.

Erosion immediately adjacent to the right and left spillway wingwalls, if not controlled, could contribute to stability problems in the spillway structure and contribute to a possible breach of the embankment.

The vertical crack in the right spillway abutment wall is evidence of movement. If the movement continues, a spillway and embankment stability problem could result.

The erosion paths and gullies, bare of vegetation from the crest to the downstream toe of the embankment, are susceptible to erosion and consequent damage, owing to runoff of rainfall.

Flow of water in the discharge channel could erode the toe of embankment on the left side of the dam and result in a stability problem of the downstream slope.

The soft, wet area approximately 20 feet downstream of the toe to the left of the spillway channel may be the result of seepage under the dam which, if not properly controlled, could lead to failure of the dam by piping.

Based on the visual inspection alone, it is not possible to determine the character of the dam and spillway foundations or the interior of the cross section of the embankment or the shape of the upstream side of the dam. Therefore, it is not possible to evaluate the factor of safety of the dam and spillway against slope failure, sliding or overturning.

6.2 Design and Construction Data. No design or construction data pertinent to the structural stability of the dam are available.

6.3 Operating Records. No operating records pertinent to the structural stability of the dam were available.

6.4 Post-Construction Changes. "Existing Conditions after Repairs and New Construction", Plan #419, dated March 27, 1947 were done by Frank D. Livermore and are on file at the New Jersey Department of Environmental Protection, Prospect Street, Trenton, New Jersey 08625.

6.5 Seismic Stability. This dam is in Seismic Zone 1. According to the Recommended Guidelines, dams located in Seismic Zone 1 "may be assumed to present no hazard from earthquake provided static stability conditions are satisfactory and conventional safety margins exist." Although no signs of unstable slopes were observed, adequate inspection was impossible because of the dense growth on the downstream crest and the downstream slopes of the dam. Because no data are available concerning the engineering properties of the embankment, foundation materials, or for the condition at the base of the corewall, it is impossible to make an engineering evaluation of the stability of the slopes or the factor of safety under static conditions.

SECTION 7
ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment

- a. Condition. Maple Lake Dam is estimated to be perhaps 80 years old and in poor overall condition.
- b. Adequacy of Information. The information available is such that the assessment of the dam must be based primarily on the results of the visual inspection.
- c. Urgency. The recommendations made in 7.2.a and 7.2.b should be implemented by the owner as prescribed.
- d. Necessity for Additional Data/Evaluation. The information available from the visual inspection is adequate to identify the potential problems which are listed in 7.2.a. These problems require the attention of a professional engineer who will have to make additional engineering studies to design or specify remedial measures to rectify the problems. If left unattended, the problems could lead to failure of the dam.

7.2 Recommendations/Remedial Measures

- a. Recommendations. The owner should retain a professional engineer qualified in the design and construction of dams to accomplish the following in the time periods specified:

Immediately:

Design and oversee procedures for the removal of trees, vines, and brush from the upstream and downstream slopes and for a distance of 25 feet from the downstream toe of the dam or limits of property, whichever is less.

Starting Soon:

1. Design and oversee repairs for the eroded areas on the downstream slope adjacent to the spillway, along the toe, and at the footpaths near the steel grating stairway.
2. Design necessary remedial measures to prevent erosion of the toe by water flowing in the discharge channel downstream from the spillway.
3. Design or specify repairs for the erosion of the upstream slope of the dam and design and specify erosion protection for the upstream slope of the dam.

4. Investigate the cause of the wet, soft area 20 feet downstream from the toe of the dam near the left bank of the spillway channel.
5. Design or specify reconstruction of the spillway and abutment walls.
6. Design or specify repairs to the low level outlet.
7. Design and oversee repairs to the cracked concrete core walls and upstream concrete walls.

In the near Future:

1. Perform a more detailed hydrologic/hydraulic evaluation of the inadequacy of the spillway and design and implement necessary increased capacity.
2. Backfill animal burrows with properly selected materials.

b. Operating and Maintenance Procedures. The owner should accomplish the following very soon.

1. Start a program of checking the condition of the dam periodically and monitoring the wet area downstream from the toe of the downstream slope.
2. Clear trees and brush from the discharge channel and from a zone 25 feet on either side of the discharge channel or to the property line, whichever is the lesser distance, from the spillway stilling basin to the next pond downstream.
3. Control trespassing on dam.
4. Start a program for maintaining the embankment free of weeds, brush, vines, and trees.


Starting Soon:

Develop an emergency action plan which outlines actions taken by the owner to minimize downstream effects of an emergency at the dam.


5. Repair steel stairs on downstream face of dam.

In the near Future:


Develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.



PLAN



PROFILE




Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST PHILADELPHIA	
BOSTON		CORPS OF ENGINEERS	
MASSACHUSETTS		PHILADELPHIA, PA	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
MAPLE LAKE DAM			
GOFFLE BROOK		NEW JERSEY	
		SCALE NOT TO SCALE	
		DATE: JUNE 1981	

FIGURE -1



SCALE IN MILES



MAP BASED ON STATE OF NEW JERSEY
OFFICIAL MAP & GUIDE.

Anderson-Nichols & Co., Inc.

BOSTON

MASSACHUSETTS

U.S. ARMY ENGINEER DIST. PHILADELPHIA
CORPS OF ENGINEERS
PHILADELPHIA, PA.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

MAPLE LAKE DAM LOCATION MAP

GOFFLE BROOK

NEW JERSEY

SCALE: 1" = 4 Miles Approx.

DATE: JUNE 1941

FIGURE - 1

APPENDIX 1
ENGINEERING AND
EXPERIENCE DATA
MAPLE LAKE DAM

April 5, 1957


Mr. Garfield E. Avejarde
Maple Lake Club
Box Maple Drive
Bychkoff, New Jersey
Re: Sewer Relocation Eas. App

Dear Mr. Avejarde:

This is in reply to your recent letter relative to your proposal to relocate Coffie Brook, near the point where it enters Maple Lake, near Bortenslyke, in Bergen County.

Kindly forward a map or sketch of your property and indicate thereon the extent and location of the proposed relocation. Upon receipt of this information, you will be advised further.

Very truly yours,


George S. Ranklin
Chief Engineer and
Acting Director

SGS:mms



DRAINING PERMIT

Effective Date--March 18, 1957

TO WHOM IT MAY CONCERN:

Pursuant to the provisions of Section 2315-29,
Revised Statutes, permission is hereby granted to

E. G. AVOLARDO
804 Maple Drive
Wyckoff, New Jersey

to drain the waters of Maple Lake, for the purpose of cleaning
and making necessary repairs, under the supervision of Warden
Garret Westerveld, provided measures are taken to prevent the
destruction of the fish.

This permit expires April 18, 1957.

Director

JVM
cc. Westerveld
Water Policy
Fisheries Lab.

March 4, 1929

Mr. E. O. Avogadro
204 Maple Drive
Wyckoff, New Jersey

Re: Dam Application No. 433

Dear Sir:

This Division has been advised that you are contemplating repairs to the Maple Lake Dam across Goffle Brook, near Wertenzyke, in Bergen County. This dam was repaired about ten years ago by the former owners, Mr. & Mrs. John M. Bell.

Enclosed for your information is a copy of our booklet entitled, "Information for Applicants for Construction, Alteration or Repair of Dams". This booklet contains excerpts from the Statutes as well as the Rules and Regulations of this Division relative to the construction, reconstruction or repair of dams. Kindly advise the nature of repairs which you contemplate in order that a determination can be made as to the necessity for your obtaining a permit from this Division for such repairs.

Very truly yours,

Herman C. Wittwer
Assistant Chief Engineer

HCW:pm
Enc.


DAM APPLICATION NO. 119.....

NCW

N.J. DEPARTMENT OF CONSERVATION
DIVISION OF WATER POLICY & SUPPLY

ACCEPTANCE OF PERMIT FOR CONSTRUCTION OR REPAIR OF DAM

Division of Water Policy & Supply
Trenton, N. J.



Gentlemen:

We hereby acknowledge receipt of your permit issued
..... April 7, 1947..... in response to our application for
permit for the construction (or repair) of.....
across.....
at (near).....
Name of Stream

We hereby accept and agree to abide by and fulfill
the terms and conditions therein imposed in carrying out the
construction work therein authorized.

.....
Name of Applicant

.....
Address

..... April 11, 1947.....
Box 343

Dam Application No. 119
(21-57)

State of New Jersey
State Water Policy Commission
REPORT ON DAM APPLICATION

To the State Water Policy Commission,
State of New Jersey.

Gentlemen:

The application of John P. Sell, P. O. Box 313, Montendyke, N. J.

Filed August 7, 1945 for approval of plans and for a permit to repair a dam
(plans filed Jan. 7, 1947)
known as Apple Lake near Montendyke on Goffle Brook

tributary to Passaic River in Bergen County, New Jersey.

has been examined by Norman C. Mitterer, Hydraulic Engineer, ~~State of New Jersey~~.

PRINCIPAL FEATURES

Location 23.10.3.1.3	Site Inspected 4/27/45 - A.R.S. 5/13/46 - N.C.S.
Purpose of dam Semi-public swimming pool	Length of dam 355 feet
Drainage area 2.3 sq. mi.	Elevation of flow line 85.0 (U.S. Coast & Geodetic Datum)
Area of Lake 5.02 acres	Capacity of lake 3.5 Mill. gal.
Type of dam earth fill with concrete core wall	Top width 6 feet
Upstream slope Vertical concrete wall	Downstream slope 1 1/2:1 approx.
Foundation material Unknown	Max. height 13 feet
Type of spillway Concrete wall, C = 3.5	Length of spillway 1.5 feet
Max. head on spillway 5.3 feet dam awash	
Spillway capacity 47 sec. ft. @ 121	sec. ft. per sq. mi. dam awash
Estimated maximum flood flow 1.05	sec. ft. per sq. mi. mean North & Central
Outlets other than spillway Concrete culvert 25" x 36" high	
Drawings filed by Frank D. Livermore - N. J. License 591	

It has been found that the site for the dam is suitable and the plans adequate to ensure the construction of a structure which will not be a menace to life or property. It is therefore recommended that the plans be approved and that a permit be issued, subject, however, to the following terms and conditions:—

1. That this permit does not give any property rights, either in real estate or material, nor any exclusive privileges; neither does it authorize any injury to private property nor invasion of private rights, nor any infringement of Federal, State or local laws or regulations, nor does it waive the obtaining of Federal assent, when necessary.

Form 10-10-10

Form 10-10-10

STATE OF NEW JERSEY
DEPARTMENT OF CONSERVATION
Division of Water Policy and Supply
28 WEST STATE STREET
TRENTON 2, NEW JERSEY

TRENTON, NEW JERSEY

DAM APPLICATION No. 419

APPLICATION FOR PERMIT FOR CONSTRUCTION
OR REPAIR OF DAM

John M. Sell New Jersey

May 6 19*45*

To the New Jersey State Water Policy Commission,
Gentlemen:—

In compliance with the provisions of Title 58, Chapter 4, Revised Statutes
(*John M. Sell* *owner* *of* *the* *dam* *known* *as* *the* *Apple Lake* *dam* *in* *the* *County* *of* *Passaic* *State* *of* *New* *Jersey* *hereby* *makes* *application* *for* *the* *approval* *of* *drawings* *and* *for* *the* *issuance* *of* *a* *permit* *to* *construct* *(repair)* *a* *dam* *known* *as* *the* *Apple Lake* *dam* *in* *the* *County* *of* *Passaic* *State* *of* *New* *Jersey* *at* *a* *point* *6* *feet* *from* *the* *center* *of* *the* *dam* *for* *the* *purpose* *of* *improving* *the* *dam* *and* *as* *an* *understanding* *draw* *in* *accordance* *with* *the* *following* *information* *and* *with* *the* *complete* *specifications* *and* *drawings* *filed* *with* *this* *application* *and* *made* *part* *hereof* *as* *follows* :

Area of water shed *28* square miles
Maximum depth of lake *6 1/2* feet
Area of water surface *0* acres
Capacity of spillway at *400* feet head, *2* cubic feet per second
The character of the foundation material is *Granite & blint*

As determined by *John M. Sell*

APPENDIX 2

CHECK LIST

VISUAL INSPECTION

MAPLE LAKE DAM

Check List
Visual Inspection
Phase I

Name Dam Maple Lake County Bergen State NJ (00776) Coordinators NJDEP
 Date(s) Inspection 2/17/81 4/23/81 Weather' Rain Rain Temperature 50 ° 55 °
 Pool Elevation at Time of Inspection 285 NGVD Tailwater at Time of Inspection 276.3 NGVD

Inspection Personnel:

<u>Guinan</u>	<u>Murdock</u>
<u>Stone</u>	
<u>Gilman</u>	

Gilman/Stone Recorder

The owner was not present during inspection.

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Right side - several transverse hairline cracks thru apron and 2 ft wall. Surface of concrete is eroded to expose coarse aggregate. 3 ft d/s concrete wall visible in few places. Some cracking and spalling on right end. Left side - u/s concrete wall has 4 transverse cracks, with one badly spalled and eroded. Surface laitance eroded from all concrete.	Repair cracking
STRUCTURAL CRACKING	Several transverse hairline cracks.	Repair cracking
VERTICAL AND HORIZONTAL ALIGNMENT	No indication of movement.	
MONOLITH JOINTS	Not visible.	
CONSTRUCTION JOINTS	Steel stairs on d/s right side - Steel treads, stringers and railing badly corroded.	

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Concrete abutments are badly spalled, cracked and eroded. Poor condition. Top of weir is spalled and eroded exposing 6-in cable. D/s face is surface eroded with a vertical crack near center that is eroded to a depth of 2 inches ±.	Major reconstruction required.
APPROACH CHANNEL	Maple Lake	
DISCHARGE CHANNEL	Concrete wall at d/s of stilling basin is surface eroded 3/4 inch exposing coarse aggregate - Rock debris.	
BRIDGE AND PIERS OVER SPILLWAY		Not applicable.

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Valve of unknown diameter, some spalling. Concrete on the u/s and d/s of the intake and discharge conduit is badly spalled and eroded.	Repair concrete
INTAKE STRUCTURE	Concrete is spalled and chamber is filled with debris. Valve stem visible under water.	Repair concrete
OUTLET PIPE	1 ft x 2 1/2 ft. End covered with debris.	Clear
OUTLET CHANNEL	Rocky and filled with debris.	Clear
EMERGENCY GATE	Not visible.	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	Spalled and cracked corewall on right (south) side.	Repair concrete
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Erosion gullies of widths up to 3 feet, 4 to 8 inches deep have developed on the d/s slope.	Repair erosion and provide adequate erosion protection.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Not applicable	
RIPRAP FAILURES	Not applicable	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
RAILINGS	None	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Erosion adjacent to both right and left spillway wingwalls. Cracks in right training wall of spillway.	Repair erosion and provide adequate erosion protection, repair cracks.
ANY NOTICEABLE SEEPAGE	None	
STAFF GAGE AND RECORDER	None	
DRAINS	None	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

CONDITION
(CESTRUCTIONS,
DEBRIS, ETC.)

Some debris, dam 200 feet d/s.
No pond behind it.

SLOPES

Steep on right, mild low slope on
left.

APPROXIMATE NO. OF HOMES AND POPULATION

1 house - estimate 6 persons.

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

Appear stable

SEDIMENTATION

No evidence of significant sedimentation was observed.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
------	---------

PLAN OF DAM	Plan #419 "Existing conditions after repairs and new construction" filed March 27, 1947 are on file at the New Jersey Department of Environmental Protection, Prospect Street, Trenton, New Jersey 08625
-------------	--

REGIONAL VICINITY MAP	Prepared for this report
-----------------------	--------------------------

CONSTRUCTION HISTORY	None found
----------------------	------------

TYPICAL SECTIONS OF DAM	Existing spillway, new concrete cap and new concrete addition. See "PLAN OF DAM" above.
-------------------------	---

HYDROLOGIC/HYDRAULIC DATA	None found
---------------------------	------------

OUTLETS - PLAN	None found
- DETAILS	None found
- CONSTRAINTS	None found
- DISCHARGE RATINGS	None found

RAINFALL/RESERVOIR RECORDS	None found
----------------------------	------------

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	None
HIGH POOL RECORDS	None
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	None

ITEM	REMARKS
DESIGN REPORTS	None found
GEOLOGY REPORTS	None found
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None found
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None found

POST-CONSTRUCTION SURVEYS OF DAM See "PLAN OF DAM" on previous page

BORROW SOURCES Unknown

ITEMS	REMARKS
SPILLWAY PLAN	See "PLAN OF DAM"
SECTIONS	None
DETAILS	None
OPERATING EQUIPMENT PLANS & DETAILS	None

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 2.21 square miles, woods, small urban area

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 285' NGVD (38.4 acre-feet)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY) Not applicable

ELEVATION MAXIMUM TESTFLOOD POOL: 289.3' NGVD

ELEVATION TOP DAM: 287.9' NGVD

SPILLWAY CREST: Uncontrolled concrete

a. Elevation 285' NGVD

b. Type Broad crested

c. Width 2.4 feet

d. Length 48 feet

e. Location Spillover Center of dam

f. Number and Type of Gates None

OUTLET WORKS: Low level outlet

a. Type Estimated 12-inch pipe contained in a
1 foot x 2.5 foot concrete box

b. Location Next to spilling basin on downstream side

HYDROMETEOROLOGICAL GAGES: None

MAXIMUM NON-DAMAGING DISCHARGE: 711 cfs

APPENDIX 3

PHOTOGRAPHS

MAPLE LAKE DAM



April 23, 1981

View of upstream face of dam at right abutment;
dam appears to have a 2-ft wide corewall.



April 23, 1981

View along corewall toward left abutment.



April 23, 1981

View erosion along left side of spillway channel.



April 23, 1981

View of downstream channel where it joins adjacent pond below bridge



April 23, 1961

View of low-level outlet hidden behind stones. Concrete casing of low-level pipe is clearly visible, extending d/s from face of spillway.



April 23, 1961

View of contact between spillway and training wall on left (north side).



April 23, 1951

Close-up view of crack and spalling in spillway d/s face.




April 23, 1951

View of extensive root growth downstream of right side of dam.

APPENDIX 4

HYDROLOGIC COMPUTATIONS

MAPLE LAKE DAM



**NATIONAL PROGRAM OF INSPECTION OF
NON-FED. DAMS**


MAPLE LAKE DAM
WYCKOFF TOWNSHIP, NEW JERSEY
REGIONAL VICINITY MAP

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA


Anderson-Nichols & Company, Inc.

BOSTON, MA.

SCALE IN MILES



MAP BASED ON U.S.G.S. 7.5 MINUTE QUADRANGLE
SHEETS. RAMSEY, N.J., N.Y. 1955, AND PATERSON,
N.J., 1955, REVISED 1970.



ANDERSON-NICHOLS

VERNON	BOSTON	CONCORD
SM	MAPLE LAKE	D/S FACE
DATE 5/11/71	SCALE:	JOB NO.
		SHEET NO. 1 OF 14

JOB NO. 3671-08

QUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

DEVELOPMENT OF RATING CURVE

$$Q = CLH^{3/2}$$

1) SPILLWAY CURVE

C = 3.0 BREADTH = 2.4 ft


WEIR LENGTH = 48 ft

2) TOP OF DAM

C = 2.6 BREADTH = 15 ft

WEIR LENGTH = 242 ft (w/o spillway)

	ELEVATION (FT. NGVD)	SPILLWAY		TOP OF DAM		COMBINED CFS (275)
		HEAD (FT)	CFS	HEAD (FT)	CFS	
18 SPILLWAY	285	0	0			
19	287.0	2.0	407			407
20 TOP DAM	287.1	2.9	711			711
21	289.1	3.1	786	0.2	138	924
22	292.4	3.4	903	0.5	290	1193
23	294.8	4.8	1514	1.9	310	1824
24	296.0	5.0	1610	2.1	327	1937
25	2910	6.0	2110	3.1	334	2444
26	2920	7.0	2667	4.1	3425	3092
27	2930	8.0	3258	5.1	3525	3783
28	2940	9.0	3888	6.1	361	4549
29	2950	10.0	4554	7.1	4505	5459



JOB NO. 3671-08SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALETIME OF CONCENTRATIONMETHOD #1 TEXAS HIGHWAY METHODOVERLAND FLOW

REACH LENGTH = 4000 ft

SLOPE = $\frac{560-350}{4000} = 0.053 = 5.3\%$

FROM TABLE "WOODLANDS"

AVG. VELOCITY $V = 2.0$ fps

4000 ft \div 2.0 fps = 2000 sec = 33.3 min

CHANNEL FLOW

REACH LENGTH = 8800 ft

SLOPE = $\frac{350-256}{8800} = .0073 = .73\%$

FROM TABLE, AVG VELOCITY $V = 2.0$ fps

8800 ft \div 2.0 fps = 4400 sec = 73.3 min

$T_C = 33.3 \text{ min} + 73.3 \text{ min} = 106.6 \text{ min} = \underline{1.8 \text{ hrs}}$

METHOD #2 SOIL AND WATER CONSERVATION

$L = 0.6 T_C$ $L = \frac{1.48 (S+1)^{1.67}}{9000 V^{1.5}}$ $S = \frac{10.22}{3.1} = 3.3$

TAKE $CN = 70$ FOR WOODS $S = \frac{10.22}{70} = 10 = 43$

$L = 4000 + 8800 = 12800 \text{ ft}$ $V = \frac{560-256}{(12800)} = .0212$

$L = \frac{(12800)^{0.8} (4.3+1)^{1.67}}{9000 (2.1)^{1.5}} = 2.40 \text{ hrs}$

$T_C = \frac{2.40}{.6} = \underline{4.0 \text{ hrs}}$

JOB NO. 3671-08

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

1

2

METHOD #3 SCS TR #55

3

4

OVERLAND FLOW

5

6

LENGTH = 4000 ft

7

HEAD = 210 ft

8

SLOPE = .053 = 5.3 %

9

10

FROM FIGURE AVG VEL. = .67 fps

11

 $T_c = \frac{4000 \text{ ft}}{3600 (.67) \text{ fps}} = 1.7 \text{ hrs}$

12

13

14

CHANNEL FLOW

15

16

LENGTH = 8800 ft

17

HEAD = 54 ft

18

SLOPE = .0073 = .73 %

19

n = .04

20

21

 $V = \frac{1.49}{n} R^{2/3} S^{1/2}$

22

(Assume a 5' x 2' rectangular channel to collect runoff)

23

24

 $R = \frac{\text{Area}}{\text{wetted perimeter}} = \frac{10}{2.236} = 4.47 \text{ ft}$

25

26

 $V = \frac{1.49}{.04} (4.47)^{2/3} (.0073)^{1/2} = 3.41 \text{ fps}$

27

28

 $T_c = \frac{8800 \text{ ft}}{3.41 \text{ fps}} = 2580.6 \text{ sec} = .72 \text{ hr}$

29

30

31

Total $T_c = 1.7 \text{ hrs} + .72 \text{ hrs} = 2.4 \text{ hrs}$

32

33

34

35

36

37

38

39

40

JOB NO. 3671-08SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALEMETHOD #4 KIRBY METHODOVERLAND FLOW

$$T_c = 0.83 \left(\frac{Nl}{\sqrt{S}} \right)^{0.467}$$

$$N = .6$$

$$S = .053$$

$$l = 4000$$

$$T_c = 0.83 \left(\frac{(.6)(4000)}{\sqrt{.053}} \right)^{0.467}$$

$$= 62.4 \text{ min} = 1.04 \text{ hrs.}$$

CHANNEL FLOW

USE MANNING AS IN METHOD #5

$$V = 3.41 \text{ fps}$$

$$T_c = \frac{86400 \text{ ft}}{3.41 \text{ fps}} = 2580.6 \text{ sec} = .72 \text{ hr}$$

$$\text{TOTAL } T_c = 1.04 \text{ hrs} + .72 \text{ hrs} = \underline{1.8 \text{ hrs}}$$

AVERAGE T_c FROM 4 METHODS:

$$\frac{1.8 \text{ hrs} + 4.0 \text{ hrs} + 2.4 \text{ hrs} + 1.8 \text{ hrs}}{4} = 2.5 \text{ hrs}$$

$$T_{c \text{ ave}} = 2.5 \text{ hrs.}$$

$$T_L = .6 T_c$$

$$T_L = \underline{1.5 \text{ hrs}}$$

JOB NO. 3671-08SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29
1/4 IN. SCALESTAGE - STORAGE DETERMINATIONSTAKE DEPTH OF LAKE TO BE 6 FT

ELEVATION FT	SURFACE AREA ACRES	AVG S-A ACRES	INCREMENTAL STORAGE AC-FT	CUMULATIVE STORAGE AC-FT
285	6.4	6.4	38.4	38.4
290	12.8	9.6	48	86.4
300	38.4	25.6	256	342.4

INPUT FOR HEC I (FROM CURVE)STAGESTORAGE

274.0

0

285.0

38.4

287.9

57.5

288.3

63.0

289.8

85.0

290.0


86.4

295.0

185.0

300.0

342.4



JOB NO. 3671-08SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
4 IN. SCALE

DETERMINATION OF Q FOR
LOW LEVEL OUTLET

D = DIAMETER = 12 INCHES (ASSUMED)

n = 0.013 (K + F 6.15)

A_p = AREA OF PIPE CIRCULAR = .79 ft^2

L_p = 40 ft (ESTIMATED)

K_f = FRICTION LOSS THROUGH PIPE

$$K_f = \frac{1.49^2 n^2}{D^{4/3}} = \frac{5089 (.013)^2}{(12)^{4/3}} = .051$$

K_L = ENTRANCE LOSS TO PIPE = 0.8 (K + F 1.0)

C_p = COEFFICIENT OF DISCHARGE

$$C_p \cdot A_p \sqrt{\frac{2g}{1 + K_L + K_f}} = .79 \sqrt{\frac{64}{1 + .8 + .051}} = 5.1$$

$$C = \frac{3.14}{5.1} = \frac{3.14}{5.1} = 0.57$$

JOB NO. 3671-08SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29
1/4 IN. SCALEDRAWDOWN BY LOW LEVEL OUTLETASSUME: 1) NO SIGNIFICANT INFLOW

2) ONE 12 INCH PIPE

3) $Q_p = C_p H^{1/2} = 3.6 H^{1/2}$ 4) $\text{ACRE-FT/DAY} = 1.9835 \times Q_{\text{AVG}}$ 5) $\text{DAYS} = \Delta \text{STORAGE} / \text{DAY}$

ELEV	STORAGE (ACRE-FT)	ΔS	H^* FT	Q_p CFS	ALL Q CFS	$\frac{\text{ACRE-FT}}{\text{DAY}}$	DAYS
285	38.4		10.5	11.7			
		30.9			10.0	19.8	1.6
280	7.5		5.5	8.4			
		6.5			5.5	10.9	1.0
275	1.0		.5	2.5			
		1			1.3	2.6	0.4
274	0		0	0			


* from mid-point of pipe (274.5' ELEV)

TOTAL = 2.6 DAY

JOB NO.

JARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 IN. SCALE


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40




CROSS SECTION
 LOCATIONS
 FOR D/S
 HAZARD ANALYSIS

MAPLE LAKE DAM
X-SECTION & SMALL
DIM 300' D/S OF
MAPLE LAKE DAM
C/18/81 120' F14 SM







APPENDIX 5

HEC-1 OUTPUT

MAPLE LAKE DAM

10.....**11**.....**12**.....**13**.....**14**.....**15**.....**16**.....**17**.....**18**.....**19**.....**20**.....**21**.....**22**.....**23**.....**24**.....**25**.....**26**.....**27**.....**28**.....**29**.....**30**.....**31**.....**32**.....**33**.....**34**.....**35**.....**36**.....**37**.....**38**.....**39**.....**40**.....**41**.....**42**.....**43**.....**44**.....**45**.....**46**.....**47**.....**48**.....**49**.....**50**.....**51**.....**52**.....**53**.....**54**.....**55**.....**56**.....**57**.....**58**.....**59**.....**60**.....**61**.....**62**.....**63**.....**64**.....**65**.....**66**.....**67**.....**68**.....**69**.....**70**.....**71**.....**72**.....**73**.....**74**.....**75**.....**76**.....**77**.....**78**.....**79**.....**80**.....**81**.....**82**.....**83**.....**84**.....**85**.....**86**.....**87**.....**88**.....**89**.....**90**.....**91**.....**92**.....**93**.....**94**.....**95**.....**96**.....**97**.....**98**.....**99**.....**100**.....

[illegible]

```
*****
*****
***** FLOID HYDROGRAPH PACKAGE (HEC-1) *****
***** F E B R U A R Y 1 9 8 1 *****
*****
*****
***** R U N   D A T E 0 7 / 3 0 / 8 1   T I M E 1 4 . 1 8 . 5 2 *****
*****
*****
```

U.S. ARMY COLLEGE OF ENGINEERS
THE HYDROLOGIC ENGINEERING CENTER
609 SECOND STREET
DAVIS, CALIFORNIA 95616
(916) 440-3285 TKN (FIS) 44F-3285

 * U.S. ARMY CORP. OF ENGINEERS
 * THE HYDROLOGIC ENGINEERING CENTER
 * 600 SOUTH BRIDGES
 * DAVIS, CALIFORNIA 95616
 * (916) 440-3285 PR (FIS) 440-3285
 * *****

 * FLOOD HYDROGRAPH PACKAGE (HLC-1)
 * FEBRUARY 1981
 *
 * RUN DATE 07/30/81 TIME 14.18.52
 * *****

MAPLE LAKE DAM OVERTOPPING & BREACH ANALYSIS #K930MERVILLE A-NECO INC#
 NEW JERSEY DAM NO. 776 BERGEN COUNTY TOWNSHIP (IF WYCOFF
 0.1-0.25-0.5 MULTIPLES OF PMF FROM 24-HOUR PMF

5 10 OUTPUT CONTROL VARIABLES 2 PRINT CONTROL
 IPRT 10 PLOT CONTROL
 IPLOT 10 PLOT SCALE
 LSCALE 0 HYDROGRAPH PLOT SCALE
 YES YES PRINT DIAGNOSTIC MESSAGES
 17 HYDROGRAPH TIME DATA 5 MINUTES IN COMPUTATION INTERVAL
 1 1 0000 STARTING DATE
 2 300 NUMBER OF HYDROGRAPH ORDINATES
 2 0055 ENDING DATE
 2 0055 ENDING TIME
 COMPUTATION INTERVAL 0.08 HOURS
 TOTAL TIME BASE 24.92 HOURS

ENGLISH UNITS
 DRAINAGE AREA SQUARE MILES
 PRECIPITATION DEPTH FEET
 LENGTH ELEVATION FEET
 FLOW RATE CUBIC FEET PER SECOND
 STORAGE VOLUME ACRES-Feet
 SURFACE AREA ACRES
 TEMPERATURE DEGREES FAHRENHEIT

JP MULTI-PLAN OPTION 2 NUMBER OF PLANS

JR MULTI-RATIO OPTION 0.50
 RATIOS OF RUNOFF 0.25

8 KK *****
 * A1 *
 * *****
 SCS UNIT GRAPH COMPUTATION -EXPONENTIAL LOSS RATE

SURBASIN RUNOFF DATA

10 BA SUBBASIN CHARACTERISTICS 2.20 SUBBASIN AREA

11 BF BASE FLOW CHARACTERISTICS
 START TO 6.60 INITIAL FLOW
 RECESS 6.60 BEGIN BASE FLOW RECESS
 RECESS 1.00000 RECESS CONSTANT

PRECIPITATION DATA

12 PM PROBABLE MAXIMUM STORM INDEX PRECIPITATION
 PMF 22.00 TRANSPORTATION COEFFICIENT
 TR300 0.80 TRANSPORTATION AREA
 TR300 2.20 USE S&D DISTRIBUTION

PERCENT OF INDEX PRECIPITATION OCCURRING IN GIVEN TIME
 0-HR 24-HR 48-HR 72-HR 96-HR
 113.0 123.0 132.0 0.0 0.0

UNIFORM LOSS RATE

STRIP INITIAL LOSS RATE
 KTMP 10.00 PERCENT IMPERVIOUS AREA

SCS DIMENSIONLESS UNITGRAPH
 LAG 1.50 LAG

UNIT HYDROGRAPH ORDINATES

92 END-OF-PERIOD	1.50 LAG	INITIAL LOSS RATE	10.00 PERCENT IMPERVIOUS AREA	SCS DIMENSIONLESS UNITGRAPH	LAG
21.	25.	51.	79.	249.	309.
446.	509.	567.	598.	607.	607.
668.	646.	620.	594.	455.	413.
334.	303.	277.	212.	179.	166.
139.	123.	117.	106.	131.	124.
54.	52.	48.	44.	31.	24.
24.	22.	20.	17.	13.	11.
10.	9.	8.	7.	6.	5.
1.	0.	4.	3.	2.	1.

HYDROGRAPH AT STATION A1

DA	MON	HR	ORD	RAIN	LOSS	EXCESS	COMP	EXCESS	LOSS	EXCESS	COMP
1	1	1	1	0.01	0.01	0.00	7.	0.00	0.01	0.16	55.
2	1	2	2	0.01	0.01	0.00	7.	0.00	0.01	0.16	41.
3	1	3	3	0.01	0.01	0.00	7.	0.00	0.01	0.16	46.
4	1	4	4	0.01	0.01	0.00	7.	0.00	0.01	0.16	47.
5	1	5	5	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
6	1	6	6	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
7	1	7	7	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
8	1	8	8	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
9	1	9	9	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
10	1	10	10	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
11	1	11	11	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
12	1	12	12	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
13	1	13	13	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
14	1	14	14	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
15	1	15	15	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
16	1	16	16	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
17	1	17	17	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
18	1	18	18	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
19	1	19	19	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
20	1	20	20	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
21	1	21	21	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
22	1	22	22	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
23	1	23	23	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
24	1	24	24	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
25	1	25	25	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
26	1	26	26	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
27	1	27	27	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
28	1	28	28	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
29	1	29	29	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.
30	1	30	30	0.01	0.01	0.00	7.	0.00	0.01	0.16	40.

[illegible]

HYDROGRAPH AT STATION A1 PLAN 1. RATIO = 0.50

DA	MEAN	HEMN	QKD	FLW	DA	MON	HEMN	QKD	FLW	DA	MON	HEMN	QKD	FLW
1	0000	0000	1234	3	1	1	145	6	176	1	1	145	6	176
2	0005	0005	1235	3	2	1	150	6	190	2	1	150	6	208
3	0010	0010	1236	3	3	1	155	6	230	3	1	155	6	237
4	0015	0015	1237	3	4	1	160	6	247	4	1	160	6	289
5	0020	0020	1238	3	5	1	165	6	289	5	1	165	6	325
6	0025	0025	1239	3	6	1	170	6	365	6	1	170	6	408
7	0030	0030	1240	3	7	1	175	6	455	7	1	175	6	553
8	0035	0035	1241	3	8	1	180	6	503	8	1	180	6	605
9	0040	0040	1242	3	9	1	185	6	554	9	1	185	6	709
10	0045	0045	1243	3	10	1	190	6	605	10	1	190	6	813
11	0050	0050	1244	3	11	1	195	6	657	11	1	195	6	915
12	0055	0055	1245	3	12	1	200	6	709	12	1	200	6	1013
13	0100	0100	1246	3	13	1	205	6	813	13	1	205	6	1106
14	0105	0105	1247	3	14	1	210	6	915	14	1	210	6	1149
15	0110	0110	1248	3	15	1	215	6	1013	15	1	215	6	1150
16	0115	0115	1249	3	16	1	220	6	1106	16	1	220	6	1230
17	0120	0120	1250	3	17	1	225	6	1149	17	1	225	6	1345
18	0125	0125	1251	3	18	1	230	6	1230	18	1	230	6	1393
19	0130	0130	1252	3	19	1	235	6	1345	19	1	235	6	1457
20	0135	0135	1253	3	20	1	240	6	1457	20	1	240	6	1530
21	0140	0140	1254	3	21	1	245	6	1530	21	1	245	6	1608
22	0145	0145	1255	3	22	1	250	6	1608	22	1	250	6	1654
23	0150	0150	1256	3	23	1	255	6	1654	23	1	255	6	1712
24	0155	0155	1257	3	24	1	260	6	1712	24	1	260	6	1767
25	0200	0200	1258	3	25	1	265	6	1767	25	1	265	6	1822
26	0205	0205	1259	3	26	1	270	6	1822	26	1	270	6	1909
27	0210	0210	1300	3	27	1	275	6	1909	27	1	275	6	2018
28	0215	0215	1301	3	28	1	280	6	2018	28	1	280	6	2187
29	0220	0220	1302	3	29	1	285	6	2187	29	1	285	6	2318
30	0225	0225	1303	3	30	1	290	6	2318	30	1	290	6	2463
31	0230	0230	1304	3	31	1	295	6	2463	31	1	295	6	2619
32	0235	0235	1305	3	32	1	300	6	2619	32	1	300	6	2741
33	0240	0240	1306	3	33	1	305	6	2741	33	1	305	6	2886
34	0245	0245	1307	3	34	1	310	6	2886	34	1	310	6	3046
35	0250	0250	1308	3	35	1	315	6	3046	35	1	315	6	3190
36	0255	0255	1309	3	36	1	320	6	3190	36	1	320	6	3335
37	0300	0300	1310	3	37	1	325	6	3335	37	1	325	6	3490
38	0305	0305	1311	3	38	1	330	6	3490	38	1	330	6	3604
39	0310	0310	1312	3	39	1	335	6	3604	39	1	335	6	3748
40	0315	0315	1313	3	40	1	340	6	3748	40	1	340	6	3886
41	0320	0320	1314	3	41	1	345	6	3886	41	1	345	6	4000
42	0325	0325	1315	3	42	1	350	6	4000	42	1	350	6	4149
43	0330	0330	1316	3	43	1	355	6	4149	43	1	355	6	4271
44	0335	0335	1317	3	44	1	360	6	4271	44	1	360	6	4386
45	0340	0340	1318	3	45	1	365	6	4386	45	1	365	6	4490
46	0345	0345	1319	3	46	1	370	6	4490	46	1	370	6	4594
47	0350	0350	1320	3	47	1	375	6	4594	47	1	375	6	4697
48	0355	0355	1321	3	48	1	380	6	4697	48	1	380	6	4799
49	0400	0400	1322	3	49	1	385	6	4799	49	1	385	6	4899
50	0405	0405	1323	3	50	1	390	6	4899	50	1	390	6	4999
51	0410	0410	1324	3	51	1	395	6	4999	51	1	395	6	5099
52	0415	0415	1325	3	52	1	400	6	5099	52	1	400	6	5199
53	0420	0420	1326	3	53	1	405	6	5199	53	1	405	6	5299
54	0425	0425	1327	3	54	1	410	6	5299	54	1	410	6	5399
55	0430	0430	1328	3	55	1	415	6	5399	55	1	415	6	5499
56	0435	0435	1329	3	56	1	420	6	5499	56	1	420	6	5599
57	0440	0440	1330	3	57	1	425	6	5599	57	1	425	6	5699
58	0445	0445	1331	3	58	1	430	6	5699	58	1	430	6	5799
59	0450	0450	1332	3	59	1	435	6	5799	59	1	435	6	5899
60	0455	0455	1333	3	60	1	440	6	5899	60	1	440	6	5999
61	0500	0500	1334	3	61	1	445	6	5999	61	1	445	6	6099
62	0505	0505	1335	3	62	1	450	6	6099	62	1	450	6	6199
63	0510	0510	1336	3	63	1	455	6	6199	63	1	455	6	6299
64	0515	0515	1337	3	64	1	460	6	6299	64	1	460	6	6399
65	0520	0520	1338	3	65	1	465	6	6399	65	1	465	6	6499
66	0525	0525	1339	3	66	1	470	6	6499	66	1	470	6	6599
67	0530	0530	1340	3	67	1	475	6	6599	67	1	475	6	6699
68	0535	0535	1341	3	68	1	480	6	6699	68	1	480	6	6799
69	0540	0540	1342	3	69	1	485	6	6799	69	1	485	6	6899
70	0545	0545	1343	3	70	1	490	6	6899	70	1	490	6	6999
71	0550	0550	1344	3	71	1	495	6	6999	71	1	495	6	7099
72	0555	0555	1345	3	72	1	500	6	7099	72	1	500	6	7199
73	0600	0600	1346	3	73	1	505	6	7199	73	1	505	6	7299
74	0605	0605	1347	3	74	1	510	6	7299	74	1	510	6	7399
75	0610	0610	1348	3	75	1	515	6	7399	75	1	515	6	7499
76	0615	0615	1349	3	76	1	520	6	7499	76	1	520	6	7599
77	0620	0620	1350	3	77	1	525	6	7599	77	1	525	6	7699
78	0625	0625	1351	3	78	1	530	6	7699	78	1	530	6	7799
79	0630	0630	1352	3	79	1	535	6	7799	79	1	535	6	7899
80	0635	0635	1353	3	80	1	540	6	7899	80	1	540	6	7999
81	0640	0640	1354	3	81	1	545	6	7999	81	1	545	6	8099
82	0645	0645	1355	3	82	1	550	6	8099	82	1	550	6	8199
83	0650	0650	1356	3	83	1	555	6	8199	83	1	555	6	8299
84	0655	0655	1357	3	84	1	560	6	8299	84	1	560	6	8399
85	0700	0700	1358	3	85	1	565	6	8399	85	1	565	6	8499
86	0705	0705	1359	3	86	1	570	6	8499	86	1	570	6	8599
87	0710	0710	1400	3	87	1	575	6	8599	87	1	575	6	8699
88	0715	0715	1401	3	88	1	580	6	8699	88	1	580	6	8799
89	0720	0720	1402	3	89	1	585	6	8799	89	1	585	6	8899
90	0725	0725	1403	3	90	1	590	6	8899	90	1	590	6	8999
91	0730	0730	1404	3	91	1	595	6	8999	91	1	595	6	9099
92	0735	0735	1405	3	92	1	600	6	9099	92	1	600	6	9199
93	0740	0740	1406	3	93	1	605	6	9199	93	1	605	6	9299
94	0745	0745	1407	3	94	1	610	6	9299	94	1	610	6	9399
95	0750	0750	1408	3	95	1	615	6	9399	95	1	615	6	9499
96	0755	0755	1409	3	96	1	620	6	9499	96	1	620	6	9599
97	0800	0800	1410	3	97	1	625	6	9599	97	1	625	6	9699
98	0805	0805	1411	3	98	1	630	6	9699	98	1	630	6	9799
99	0810	0810	1412	3	99	1	635	6	9799	99	1	635	6	9899
100	0815	0815	1413	3	100	1	640	6	9899	100	1	640	6	9999

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

HYDROGRAPH AT STATION A2
PLAN 1. RATIO = 0.50

DA	MON	HR:MIN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HR:MIN	ORD	OUTFLOW	STORAGE	STAGE
1	1	0000	1	29.0	39.3	2.5	1	1	0000	1	29.0	39.3	2.5
1	1	0005	103	35.0	39.5	2.5	1	1	0005	103	35.0	39.5	2.5
1	1	0010	104	39.0	39.7	2.5	1	1	0010	104	39.0	39.7	2.5
1	1	0015	105	43.0	39.9	2.5	1	1	0015	105	43.0	39.9	2.5
1	1	0020	106	47.0	40.1	2.5	1	1	0020	106	47.0	40.1	2.5
1	1	0025	107	51.0	40.2	2.5	1	1	0025	107	51.0	40.2	2.5
1	1	0030	108	55.0	40.4	2.5	1	1	0030	108	55.0	40.4	2.5
1	1	0035	109	61.0	40.5	2.5	1	1	0035	109	61.0	40.5	2.5
1	1	0040	110	66.0	40.7	2.5	1	1	0040	110	66.0	40.7	2.5
1	1	0045	111	71.0	40.8	2.5	1	1	0045	111	71.0	40.8	2.5
1	1	0050	112	75.0	41.1	2.5	1	1	0050	112	75.0	41.1	2.5
1	1	0055	113	80.0	41.3	2.5	1	1	0055	113	80.0	41.3	2.5
1	1	0100	114	84.0	41.4	2.5	1	1	0100	114	84.0	41.4	2.5
1	1	0105	115	89.0	41.5	2.5	1	1	0105	115	89.0	41.5	2.5
1	1	0110	116	93.0	41.7	2.5	1	1	0110	116	93.0	41.7	2.5
1	1	0115	117	97.0	41.8	2.5	1	1	0115	117	97.0	41.8	2.5
1	1	0120	118	101.0	41.9	2.5	1	1	0120	118	101.0	41.9	2.5
1	1	0125	119	104.0	42.0	2.5	1	1	0125	119	104.0	42.0	2.5
1	1	0130	120	108.0	42.1	2.5	1	1	0130	120	108.0	42.1	2.5
1	1	0135	121	111.0	42.2	2.5	1	1	0135	121	111.0	42.2	2.5
1	1	0140	122	114.0	42.3	2.5	1	1	0140	122	114.0	42.3	2.5
1	1	0145	123	117.0	42.4	2.5	1	1	0145	123	117.0	42.4	2.5
1	1	0150	124	119.0	42.5	2.5	1	1	0150	124	119.0	42.5	2.5
1	1	0155	125	123.0	42.6	2.5	1	1	0155	125	123.0	42.6	2.5
1	1	0200	126	127.0	42.7	2.5	1	1	0200	126	127.0	42.7	2.5
1	1	0205	127	129.0	42.8	2.5	1	1	0205	127	129.0	42.8	2.5
1	1	0210	128	133.0	42.9	2.5	1	1	0210	128	133.0	42.9	2.5
1	1	0215	129	137.0	43.0	2.5	1	1	0215	129	137.0	43.0	2.5
1	1	0220	130	139.0	43.1	2.5	1	1	0220	130	139.0	43.1	2.5
1	1	0225	131	141.0	43.2	2.5	1	1	0225	131	141.0	43.2	2.5
1	1	0230	132	142.0	43.3	2.5	1	1	0230	132	142.0	43.3	2.5
1	1	0235	133	143.0	43.4	2.5	1	1	0235	133	143.0	43.4	2.5
1	1	0240	134	144.0	43.5	2.5	1	1	0240	134	144.0	43.5	2.5
1	1	0245	135	145.0	43.6	2.5	1	1	0245	135	145.0	43.6	2.5
1	1	0250	136	147.0	43.7	2.5	1	1	0250	136	147.0	43.7	2.5
1	1	0255	137	149.0	43.8	2.5	1	1	0255	137	149.0	43.8	2.5
1	1	0300	138	151.0	43.9	2.5	1	1	0300	138	151.0	43.9	2.5
1	1	0305	139	153.0	44.0	2.5	1	1	0305	139	153.0	44.0	2.5
1	1	0310	140	155.0	44.1	2.5	1	1	0310	140	155.0	44.1	2.5
1	1	0315	141	157.0	44.2	2.5	1	1	0315	141	157.0	44.2	2.5
1	1	0320	142	159.0	44.3	2.5	1	1	0320	142	159.0	44.3	2.5
1	1	0325	143	161.0	44.4	2.5	1	1	0325	143	161.0	44.4	2.5
1	1	0330	144	163.0	44.5	2.5	1	1	0330	144	163.0	44.5	2.5
1	1	0335	145	164.0	44.6	2.5	1	1	0335	145	164.0	44.6	2.5
1	1	0340	146	166.0	44.7	2.5	1	1	0340	146	166.0	44.7	2.5
1	1	0345	147	167.0	44.8	2.5	1	1	0345	147	167.0	44.8	2.5
1	1	0350	148	169.0	44.9	2.5	1	1	0350	148	169.0	44.9	2.5
1	1	0355	149	170.0	45.0	2.5	1	1	0355	149	170.0	45.0	2.5
1	1	0400	150	172.0	45.1	2.5	1	1	0400	150	172.0	45.1	2.5
1	1	0405	151	174.0	45.2	2.5	1	1	0405	151	174.0	45.2	2.5
1	1	0410	152	176.0	45.3	2.5	1	1	0410	152	176.0	45.3	2.5
1	1	0415	153	177.0	45.4	2.5	1	1	0415	153	177.0	45.4	2.5
1	1	0420	154	179.0	45.5	2.5	1	1	0420	154	179.0	45.5	2.5
1	1	0425	155	180.0	45.6	2.5	1	1	0425	155	180.0	45.6	2.5
1	1	0430	156	182.0	45.7	2.5	1	1	0430	156	182.0	45.7	2.5
1	1	0435	157	184.0	45.8	2.5	1	1	0435	157	184.0	45.8	2.5
1	1	0440	158	185.0	45.9	2.5	1	1	0440	158	185.0	45.9	2.5
1	1	0445	159	186.0	46.0	2.5	1	1	0445	159	186.0	46.0	2.5
1	1	0450	160	187.0	46.1	2.5	1	1	0450	160	187.0	46.1	2.5
1	1	0455	161	188.0	46.2	2.5	1	1	0455	161	188.0	46.2	2.5
1	1	0500	162	189.0	46.3	2.5	1	1	0500	162	189.0	46.3	2.5
1	1	0505	163	190.0	46.4	2.5	1	1	0505	163	190.0	46.4	2.5
1	1	0510	164	191.0	46.5	2.5	1	1	0510	164	191.0	46.5	2.5
1	1	0515	165	192.0	46.6	2.5	1	1	0515	165	192.0	46.6	2.5
1	1	0520	166	193.0	46.7	2.5	1	1	0520	166	193.0	46.7	2.5
1	1	0525	167	194.0	46.8	2.5	1	1	0525	167	194.0	46.8	2.5
1	1	0530	168	195.0	46.9	2.5	1	1	0530	168	195.0	46.9	2.5
1	1	0535	169	196.0	47.0	2.5	1	1	0535	169	196.0	47.0	2.5
1	1	0540	170	197.0	47.1	2.5	1	1	0540	170	197.0	47.1	2.5
1	1	0545	171	198.0	47.2	2.5	1	1	0545	171	198.0	47.2	2.5
1	1	0550	172	199.0	47.3	2.5	1	1	0550	172	199.0	47.3	2.5
1	1	0555	173	200.0	47.4	2.5	1	1	0555	173	200.0	47.4	2.5
1	1	0600	174	201.0	47.5	2.5	1	1	0600	174	201.0	47.5	2.5
1	1	0605	175	202.0	47.6	2.5	1	1	0605	175	202.0	47.6	2.5
1	1	0610	176	203.0	47.7	2.5	1	1	0610	176	203.0	47.7	2.5
1	1	0615	177	204.0	47.8	2.5	1	1	0615	177	204.0	47.8	2.5
1	1	0620	178	205.0	47.9	2.5	1	1	0620	178	205.0	47.9	2.5
1	1	0625	179	206.0	48.0	2.5	1	1	0625	179	206.0	48.0	2.5
1	1	0630	180	207.0	48.1	2.5	1	1	0630	180	207.0	48.1	2.5
1	1	0635	181	208.0	48.2	2.5	1	1	0635	181	208.0	48.2	2.5
1	1	0640	182	209.0	48.3	2.5	1	1	0640	182	209.0	48.3	2.5
1	1	0645	183	210.0	48.4	2.5	1	1	0645	183	210.0	48.4	2.5
1	1	0650	184	211.0	48.5	2.5	1	1	0650	184	211.0	48.5	2.5
1	1	0655	185	212.0	48.6	2.5	1	1	0655	185	212.0	48.6	2.5
1	1	0700	186	213.0	48.7	2.5	1	1	0700	186	213.0	48.7	2.5
1	1	0705	187	214.0	48.8	2.5	1	1	0705	187	214.0	48.8	2.5
1	1	0710	188	215.0	48.9	2.5	1	1	0710	188	215.0	48.9	2.5
1	1	0715	189	216.0	49.0	2.5	1	1	0715	189	216.0	49.0	2.5
1	1	0720	190	217.0	49.1	2.5	1	1	0720	190	217.0	49.1	2.5
1	1	0725	191	218.0	49.2	2.5	1	1	0725	191	218.0	49.2	2.5
1	1	0730	192	219.0	49.3	2.5	1	1	0730	192	219.0	49.3	2.5
1	1	0735	193	220.0	49.4	2.5	1	1	0735	193	220.0	49.4	2.5
1	1	0740	194	221.0	49.5	2.5	1	1	0740	194	221.0	49.5	2.5
1	1	0745	195	222.0	49.6	2.5	1	1	0745	195	222.0	49.6	2.5
1	1	0750	196	223.0	49.7	2.5	1	1	0750	196	223.0	49.7	2.5
1	1	0755	197	224.0	49.8	2.5	1	1	0755	197	224.0	49.8	2.5
1	1	0800	198	225.0	49.9	2.5	1	1	0800	198	225.0	49.9	2.5
1	1	0805	199	226.0	50.0	2.5	1	1	0805	199	226.0	50.0	2.5
1	1	0810	200	227.0	50.1	2.5	1	1	0810	200	227.0	50.1	2.5
1	1	0815	201	228.0	50.2	2.5	1	1	0815	201	228.0	50.2	2.5
1	1	0820	202	229.0	50.3	2.5	1	1	0820	202	229.0	50.3	2.5
1	1	0825	203	230.0	50.4	2.5	1	1	0825	203	230.0	50.4	2.5
1	1	0830	204	231.0	50.5	2.5	1	1	0830	204	231.0	50.5	2.5
1	1	0835	205	232.0	50.6	2.5	1	1	0835	205	232.0	50.6	2.5
1	1	0840	206	233.0	50.7	2.5	1						

HYDROGRAPH AT STATION 0.50 A7 PLAN 2.

CA MCN	HRMN	ORD	OUTFLW	STDRGE	STAGE	UA	MON	HRMN	ORD	OUTFLW	STDRGE	STAGE
0000	0000	1	0	38.4	265.0	1	1600	201	3218	311	2.8	242.9
0005	0005	2	1	38.4	265.0	1	1605	203	3319	312	2.8	243.1
0010	0010	3	1	38.4	265.0	1	1610	205	3420	313	2.8	243.3
0015	0015	4	2	38.4	265.0	1	1615	207	3521	314	2.8	243.5
0020	0020	5	2	38.4	265.0	1	1620	209	3622	315	2.8	243.7
0025	0025	6	3	38.4	265.0	1	1625	211	3723	316	2.8	243.9
0030	0030	7	3	38.4	265.0	1	1630	213	3824	317	2.8	244.1
0035	0035	8	3	38.4	265.0	1	1635	215	3925	318	2.8	244.3
0040	0040	9	4	38.4	265.0	1	1640	217	4026	319	2.8	244.5
0045	0045	10	4	38.4	265.0	1	1645	219	4127	320	2.8	244.7
0050	0050	11	4	38.4	265.0	1	1650	221	4228	321	2.8	244.9
0055	0055	12	4	38.4	265.0	1	1655	223	4329	322	2.8	245.1
0060	0060	13	4	38.4	265.0	1	1660	225	4430	323	2.8	245.3
0065	0065	14	4	38.4	265.0	1	1665	227	4531	324	2.8	245.5
0070	0070	15	4	38.4	265.0	1	1670	229	4632	325	2.8	245.7
0075	0075	16	4	38.4	265.0	1	1675	231	4733	326	2.8	245.9
0080	0080	17	4	38.4	265.0	1	1680	233	4834	327	2.8	246.1
0085	0085	18	4	38.4	265.0	1	1685	235	4935	328	2.8	246.3
0090	0090	19	4	38.4	265.0	1	1690	237	5036	329	2.8	246.5
0095	0095	20	4	38.4	265.0	1	1695	239	5137	330	2.8	246.7
0100	0100	21	4	38.4	265.0	1	1700	241	5238	331	2.8	246.9
0105	0105	22	4	38.4	265.0	1	1705	243	5339	332	2.8	247.1
0110	0110	23	4	38.4	265.0	1	1710	245	5440	333	2.8	247.3
0115	0115	24	4	38.4	265.0	1	1715	247	5541	334	2.8	247.5
0120	0120	25	4	38.4	265.0	1	1720	249	5642	335	2.8	247.7
0125	0125	26	4	38.4	265.0	1	1725	251	5743	336	2.8	247.9
0130	0130	27	4	38.4	265.0	1	1730	253	5844	337	2.8	248.1
0135	0135	28	4	38.4	265.0	1	1735	255	5945	338	2.8	248.3
0140	0140	29	4	38.4	265.0	1	1740	257	6046	339	2.8	248.5
0145	0145	30	4	38.4	265.0	1	1745	259	6147	340	2.8	248.7
0150	0150	31	4	38.4	265.0	1	1750	261	6248	341	2.8	248.9
0155	0155	32	4	38.4	265.0	1	1755	263	6349	342	2.8	249.1
0160	0160	33	4	38.4	265.0	1	1760	265	6450	343	2.8	249.3
0165	0165	34	4	38.4	265.0	1	1765	267	6551	344	2.8	249.5
0170	0170	35	4	38.4	265.0	1	1770	269	6652	345	2.8	249.7
0175	0175	36	4	38.4	265.0	1	1775	271	6753	346	2.8	249.9
0180	0180	37	4	38.4	265.0	1	1780	273	6854	347	2.8	250.1
0185	0185	38	4	38.4	265.0	1	1785	275	6955	348	2.8	250.3
0190	0190	39	4	38.4	265.0	1	1790	277	7056	349	2.8	250.5
0195	0195	40	4	38.4	265.0	1	1795	279	7157	350	2.8	250.7
0200	0200	41	4	38.4	265.0	1	1800	281	7258	351	2.8	250.9
0205	0205	42	4	38.4	265.0	1	1805	283	7359	352	2.8	251.1
0210	0210	43	4	38.4	265.0	1	1810	285	7460	353	2.8	251.3
0215	0215	44	4	38.4	265.0	1	1815	287	7561	354	2.8	251.5
0220	0220	45	4	38.4	265.0	1	1820	289	7662	355	2.8	251.7
0225	0225	46	4	38.4	265.0	1	1825	291	7763	356	2.8	251.9
0230	0230	47	4	38.4	265.0	1	1830	293	7864	357	2.8	252.1
0235	0235	48	4	38.4	265.0	1	1835	295	7965	358	2.8	252.3
0240	0240	49	4	38.4	265.0	1	1840	297	8066	359	2.8	252.5
0245	0245	50	4	38.4	265.0	1	1845	299	8167	360	2.8	252.7
0250	0250	51	4	38.4	265.0	1	1850	301	8268	361	2.8	252.9
0255	0255	52	4	38.4	265.0	1	1855	303	8369	362	2.8	253.1
0260	0260	53	4	38.4	265.0	1	1860	305	8470	363	2.8	253.3
0265	0265	54	4	38.4	265.0	1	1865	307	8571	364	2.8	253.5
0270	0270	55	4	38.4	265.0	1	1870	309	8672	365	2.8	253.7
0275	0275	56	4	38.4	265.0	1	1875	311	8773	366	2.8	253.9
0280	0280	57	4	38.4	265.0	1	1880	313	8874	367	2.8	254.1
0285	0285	58	4	38.4	265.0	1	1885	315	8975	368	2.8	254.3
0290	0290	59	4	38.4	265.0	1	1890	317	9076	369	2.8	254.5
0295	0295	60	4	38.4	265.0	1	1895	319	9177	370	2.8	254.7
0300	0300	61	4	38.4	265.0	1	1900	321	9278	371	2.8	254.9
0305	0305	62	4	38.4	265.0	1	1905	323	9379	372	2.8	255.1
0310	0310	63	4	38.4	265.0	1	1910	325	9480	373	2.8	255.3
0315	0315	64	4	38.4	265.0	1	1915	327	9581	374	2.8	255.5
0320	0320	65	4	38.4	265.0	1	1920	329	9682	375	2.8	255.7
0325	0325	66	4	38.4	265.0	1	1925	331	9783	376	2.8	255.9
0330	0330	67	4	38.4	265.0	1	1930	333	9884	377	2.8	256.1
0335	0335	68	4	38.4	265.0	1	1935	335	9985	378	2.8	256.3
0340	0340	69	4	38.4	265.0	1	1940	337	10086	379	2.8	256.5
0345	0345	70	4	38.4	265.0	1	1945	339	10187	380	2.8	256.7
0350	0350	71	4	38.4	265.0	1	1950	341	10288	381	2.8	256.9
0355	0355	72	4	38.4	265.0	1	1955	343	10389	382	2.8	257.1
0360	0360	73	4	38.4	265.0	1	1960	345	10490	383	2.8	257.3
0365	0365	74	4	38.4	265.0	1	1965	347	10591	384	2.8	257.5
0370	0370	75	4	38.4	265.0	1	1970	349	10692	385	2.8	257.7
0375	0375	76	4	38.4	265.0	1	1975	351	10793	386	2.8	257.9
0380	0380	77	4	38.4	265.0	1	1980	353	10894	387	2.8	258.1
0385	0385	78	4	38.4	265.0	1	1985	355	10995	388	2.8	258.3
0390	0390	79	4	38.4	265.0	1	1990	357	11096	389	2.8	258.5
0395	0395	80	4	38.4	265.0	1	1995	359	11197	390	2.8	258.7
0400	0400	81	4	38.4	265.0	1	2000	361	11298	391	2.8	258.9
0405	0405	82	4	38.4	265.0	1	2005	363	11399	392	2.8	259.1
0410	0410	83	4	38.4	265.0	1	2010	365	11500	393	2.8	259.3
0415	0415	84	4	38.4	265.0	1	2015	367	11601	394	2.8	259.5
0420	0420	85	4	38.4	265.0	1	2020	369	11702	395	2.8	259.7
0425	0425	86	4	38.4	265.0	1	2025	371	11803	396	2.8	259.9
0430	0430	87	4	38.4	265.0	1	2030	373	11904	397	2.8	260.1
0435	0435	88	4	38.4	265.0	1	2035	375	12005	398	2.8	260.3
0440	0440	89	4	38.4	265.0	1	2040	377	12106	399	2.8	260.5
0445	0445	90	4	38.4	265.0	1	2045	379	12207	400	2.8	260.7
0450	0450	91	4	38.4	265.0	1	2050	381	12308	401	2.8	260.9
0455	0455	92	4	38.4	265.0	1	2055	383	12409	402	2.8	261.1
0460	0460	93	4	38.4	265.0	1	2060	385	12510	403	2.8	261.3
0465	0465	94	4	38.4	265.0	1	2065	387	12611	404	2.8	261.5
0470	0470	95	4	38.4	265.0	1	2070	389	12712	405	2.8	261.7
0475	0475	96	4	38.4	265.0	1	2075	391	12813	406	2.8	261.9
0480	0480	97	4	38.4	265.0	1	2080	393	12914	407	2.8	262.1
0485	0485	98	4	38.4	265.0	1	2085	395	13015	408	2.8	262.3
0490	0490	99	4	38.4	265.0	1	2090	397	13116	409	2.8	262.5
0495	0495	100	4	38.4	265.0	1	2095	399	13217	410	2.8	262.7

1	0755	96	18.	39.0	265.1	1	1615	196	2473.	26.7	281.6	2	0035	296	59.	274.7
1	0800	97	20.	39.0	285.1	1	1620	197	2631.	27.7	281.9	2	0040	297	59.	274.6
1	0805	98	21.	39.1	285.1	1	1625	198	2751.	28.7	282.2	2	0045	298	50.	274.6
1	0810	99	24.	39.2	265.1	1	1630	199	2949.	29.6	282.5	2	0050	299	50.	274.6
1	0815	100	26.	39.2	265.1	1	1635	200	3093.	30.5	282.7	2	0055	300	49.	274.6

PEAK OUTFLOW IS 5563. AT TIME 14.02 HOURS

PEAK FLOW (CFS) 4139.	TIME (HR) 14.00	6-HR 2179.	MAXIMUM AVERAGE FLOW 24-HR 634.	24.92-HR 611.
(INCHES) (AC-FT)		9.209 1061.	10.725 1259.	10.727 1259.
PEAK STORAGE (AC-FT) 56.	TIME (HR) 13.94	6-HR 44.	MAXIMUM AVERAGE STORAGE 24-HR 31.	24.92-HR 30.
PEAK STAGE (FEET) 267.91	TIME (HR) 13.94	6-HR 265.78	MAXIMUM AVERAGE STAGE 24-HR 282.63	24.92-HR 282.34

CUMULATIVE AREA = 2.20 SQ MI

CHANNEL ROUTING-MOD PULS-AT SMALL DAM

26 KK *****
A3

27 NO OUTPUT CONTROL VARIABLES
PRINT CONTROL
PLOT CONTROL
HYDROGRAPH PLOT SCALE

HYDROGRAPH ROUTING DATA

28 AS STORAGE ROUTING
STEPS
ITYP
RSVRIC
X

1 NUMBER OF SUBREACHES
TYPE OF INITIAL CONDITION
INITIAL CONDITION
WORKING R AND D COEFFICIENT

29 RC NORMAL DEPTH CHANNEL ROUTING
ANCH
ANCH
ANCH
RLNTH
SEL
ELMAX

LEFT OVERTANK N-VALUE
MAIN CHANNEL N-VALUE
RIGHT OVERTANK N-VALUE
REACH LENGTH
ENERGY SLOPE
MAX. ELEV. FOR STORAGE/OUTFLOW CALCULATION

30 ELEVATION
DISTANCE

31 ELEVATION
DISTANCE

CROSS-SECTION DATA
LEFT OVERTANK
MAIN CHANNEL
RIGHT OVERTANK

STORAGE 0.0 0.27 0.63 1.08 1.63 2.27 2.91 3.66 4.46 5.34
 OUTFLOW 0.0 165.18 574.78 1253.40 2365.47 3825.00 5606.55 7722.48 10174.50 12956.50
 ELEVATION 16110.69 19665.90 23634.62 28032.43 32674.40 38176.47 43954.45 50223.82 57000.07 64298.45
 272.09 272.95 273.89 274.84 275.78 276.71 277.68 278.63 279.58 280.53
 281.49 282.42 283.37 284.31 285.26 286.21 287.16 288.10 289.05 290.03

*** WARNING *** MODIFIED PULS ROUTING WILL BE NUMERICALLY UNSTABLE FOR OUTFLOWS BETWEEN 0. TO 64298.
 USE SHORTER TIME INTERVAL OR LONGER REACH LENGTH

HYDROGRAPH AT STATION A3
 FOR PLAN 1. RATIO = 0.10

PEAK FLOW (CFS) 1749.0
 (INCHES) 1.754
 (AC-FT) 208.0
 TIME (HR) 6.0
 MAXIMUM AVERAGE FLOW 24-HR 119.0
 72-HR 208.1
 24.92-HR 244.0

PEAK STORAGE (AC-FT) 1.0
 TIME (HR) 6.0
 MAXIMUM AVERAGE STORAGE 24-HR 0.0
 72-HR 0.0
 24.92-HR 0.0

PEAK STAGE (FEET) 274.64
 TIME (HR) 6.0
 MAXIMUM AVERAGE STAGE 24-HR 0.0
 72-HR 0.0
 24.92-HR 0.0

CUMULATIVE AREA = 2.20 SQ MI

HYDROGRAPH AT STATION A3
 FOR PLAN 1. RATIO = 0.25

PEAK FLOW (CFS) 1749.0
 (INCHES) 1.754
 (AC-FT) 208.0
 TIME (HR) 6.0
 MAXIMUM AVERAGE FLOW 24-HR 119.0
 72-HR 208.1
 24.92-HR 244.0

PEAK STORAGE (AC-FT) 1.0
 TIME (HR) 6.0
 MAXIMUM AVERAGE STORAGE 24-HR 0.0
 72-HR 0.0
 24.92-HR 0.0

PEAK STAGE (FEET) 274.64
 TIME (HR) 6.0
 MAXIMUM AVERAGE STAGE 24-HR 0.0
 72-HR 0.0
 24.92-HR 0.0

CUMULATIVE AREA = 2.20 SQ MI

HYDROGRAPH AT STATION A3
 FOR PLAN 1. RATIO = 0.50

PEAK FLOW (CFS) 3500.0
 (INCHES) 3.508
 (AC-FT) 416.0
 TIME (HR) 10.0
 MAXIMUM AVERAGE FLOW 24-HR 236.7
 72-HR 416.0
 24.92-HR 593.0

PEAK STORAGE (AC-FT) 1.0
 TIME (HR) 10.0
 MAXIMUM AVERAGE STORAGE 24-HR 0.0
 72-HR 0.0
 24.92-HR 0.0

PEAK STAGE (FEET) 274.64
 TIME (HR) 10.0
 MAXIMUM AVERAGE STAGE 24-HR 0.0
 72-HR 0.0
 24.92-HR 0.0

CUMULATIVE AREA = 2.20 SQ MI


```

*** ** HYDROGRAPH AT STATION A3
FOR PLAN 2, RATIO = 0.50
*** **
PEAK FLOW (CFS) 3716.
TIME (HR) 14.00
(CFS) 2179.
(INCHES) 9.208
(AC-FT) 1080.
MAXIMUM AVERAGE FLOW
24-HR 634.
72-HR 611.
24.92-HR 611.
MAXIMUM AVERAGE STORAGE
24-HR 0.
72-HR 0.
24.92-HR 0.
PEAK STORAGE (AC-FT) 2.
TIME (HR) 14.00
PEAK STAGE (EFF) 276.67
TIME (HR) 14.00
MAXIMUM AVERAGE STAGE
24-HR 275.28
72-HR 273.23
24.92-HR 273.23
CUMULATIVE AREA = 2.20 SQ MI

```

```

*** ** CHANNEL ROUTING-MOD PULS-AT HOUSE AND NEWTON ROAD BRIDGE
*** **
*****
* A4 *
*****

```

```

HYDROGRAPH ROUTING DATA
32 KK
33 RS
34 RC
STORAGE ROUTING
NSTYPE
TYPE
RSVRIC X
NUMBER OF SUBREACHES
TYPE OF INITIAL CONDITION
-1.00 INITIAL CONDITION
0.0 WORKING R AND O COEFFICIENT
NORMAL DEPTH CHANNEL ROUTING
ANL
ANCH
ARR
KLNTH
SEL
ELMAX
LEFT OVERBANK N-VALUE
MAIN CHANNEL N-VALUE
RIGHT OVERBANK N-VALUE
REACH LENGTH
ENERGY SLOPE
MAX. ELEV. FOR STORAGE/OUTFLOW CALCULATION

```

```

CROSS-SECTION DATA
LEFT OVERBANK
ELEVATION 260.00
DISTANCE 0.0
1300.00
269.00
1310.00
263.00
1350.00
270.00
1450.00
280.00
1700.00
RIGHT OVERBANK
ELEVATION 270.00
DISTANCE 1310.00
1350.00
1450.00
269.00
1700.00
280.00
1700.00
COMPUTED STORAGE-OUTFLOW CURVE
STORAGE 0.0 0.90 35.00 1.81 49.90 2.71 89.09 113.38 140.81 171.37 205.06 241.82
OUTFLOW 0.0 107.50 6955.46 331.87 11910.64 16950.53 999.63 22209.74 29315.60 37889.49 48047.66 59902.64 73562.94
ELEVATION 263.00 263.59 273.84 273.73 264.79 265.68 269.58 275.52 276.42 268.37 279.10 271.05 263.00

```

HYDROGRAPH AT STATION A4
PLAN I. RATIO = 0.50

DA	MIN	HEM	DRU	OUTFLW	STORAGE	STAGE	DA	MIN	HEM	DRU	OUTFLW	STORAGE	STAGE
1	1	1	1	1	0	263.0	1	1	1	1	1	0	271.0
2	2	2	2	2	0	263.0	2	2	2	2	2	0	271.0
3	3	3	3	3	0	263.0	3	3	3	3	3	0	271.0
4	4	4	4	4	0	263.0	4	4	4	4	4	0	271.0
5	5	5	5	5	0	263.0	5	5	5	5	5	0	271.0
6	6	6	6	6	0	263.0	6	6	6	6	6	0	271.0
7	7	7	7	7	0	263.0	7	7	7	7	7	0	271.0
8	8	8	8	8	0	263.0	8	8	8	8	8	0	271.0
9	9	9	9	9	0	263.0	9	9	9	9	9	0	271.0
10	10	10	10	10	0	263.0	10	10	10	10	10	0	271.0
11	11	11	11	11	0	263.0	11	11	11	11	11	0	271.0
12	12	12	12	12	0	263.0	12	12	12	12	12	0	271.0
13	13	13	13	13	0	263.0	13	13	13	13	13	0	271.0
14	14	14	14	14	0	263.0	14	14	14	14	14	0	271.0
15	15	15	15	15	0	263.0	15	15	15	15	15	0	271.0
16	16	16	16	16	0	263.0	16	16	16	16	16	0	271.0
17	17	17	17	17	0	263.0	17	17	17	17	17	0	271.0
18	18	18	18	18	0	263.0	18	18	18	18	18	0	271.0
19	19	19	19	19	0	263.0	19	19	19	19	19	0	271.0
20	20	20	20	20	0	263.0	20	20	20	20	20	0	271.0
21	21	21	21	21	0	263.0	21	21	21	21	21	0	271.0
22	22	22	22	22	0	263.0	22	22	22	22	22	0	271.0
23	23	23	23	23	0	263.0	23	23	23	23	23	0	271.0
24	24	24	24	24	0	263.0	24	24	24	24	24	0	271.0
25	25	25	25	25	0	263.0	25	25	25	25	25	0	271.0
26	26	26	26	26	0	263.0	26	26	26	26	26	0	271.0
27	27	27	27	27	0	263.0	27	27	27	27	27	0	271.0
28	28	28	28	28	0	263.0	28	28	28	28	28	0	271.0
29	29	29	29	29	0	263.0	29	29	29	29	29	0	271.0
30	30	30	30	30	0	263.0	30	30	30	30	30	0	271.0
31	31	31	31	31	0	263.0	31	31	31	31	31	0	271.0
32	32	32	32	32	0	263.0	32	32	32	32	32	0	271.0
33	33	33	33	33	0	263.0	33	33	33	33	33	0	271.0
34	34	34	34	34	0	263.0	34	34	34	34	34	0	271.0
35	35	35	35	35	0	263.0	35	35	35	35	35	0	271.0
36	36	36	36	36	0	263.0	36	36	36	36	36	0	271.0
37	37	37	37	37	0	263.0	37	37	37	37	37	0	271.0
38	38	38	38	38	0	263.0	38	38	38	38	38	0	271.0
39	39	39	39	39	0	263.0	39	39	39	39	39	0	271.0
40	40	40	40	40	0	263.0	40	40	40	40	40	0	271.0
41	41	41	41	41	0	263.0	41	41	41	41	41	0	271.0
42	42	42	42	42	0	263.0	42	42	42	42	42	0	271.0
43	43	43	43	43	0	263.0	43	43	43	43	43	0	271.0
44	44	44	44	44	0	263.0	44	44	44	44	44	0	271.0
45	45	45	45	45	0	263.0	45	45	45	45	45	0	271.0
46	46	46	46	46	0	263.0	46	46	46	46	46	0	271.0
47	47	47	47	47	0	263.0	47	47	47	47	47	0	271.0
48	48	48	48	48	0	263.0	48	48	48	48	48	0	271.0
49	49	49	49	49	0	263.0	49	49	49	49	49	0	271.0
50	50	50	50	50	0	263.0	50	50	50	50	50	0	271.0
51	51	51	51	51	0	263.0	51	51	51	51	51	0	271.0
52	52	52	52	52	0	263.0	52	52	52	52	52	0	271.0
53	53	53	53	53	0	263.0	53	53	53	53	53	0	271.0
54	54	54	54	54	0	263.0	54	54	54	54	54	0	271.0
55	55	55	55	55	0	263.0	55	55	55	55	55	0	271.0
56	56	56	56	56	0	263.0	56	56	56	56	56	0	271.0
57	57	57	57	57	0	263.0	57	57	57	57	57	0	271.0
58	58	58	58	58	0	263.0	58	58	58	58	58	0	271.0
59	59	59	59	59	0	263.0	59	59	59	59	59	0	271.0
60	60	60	60	60	0	263.0	60	60	60	60	60	0	271.0
61	61	61	61	61	0	263.0	61	61	61	61	61	0	271.0
62	62	62	62	62	0	263.0	62	62	62	62	62	0	271.0
63	63	63	63	63	0	263.0	63	63	63	63	63	0	271.0
64	64	64	64	64	0	263.0	64	64	64	64	64	0	271.0
65	65	65	65	65	0	263.0	65	65	65	65	65	0	271.0
66	66	66	66	66	0	263.0	66	66	66	66	66	0	271.0
67	67	67	67	67	0	263.0	67	67	67	67	67	0	271.0
68	68	68	68	68	0	263.0	68	68	68	68	68	0	271.0
69	69	69	69	69	0	263.0	69	69	69	69	69	0	271.0
70	70	70	70	70	0	263.0	70	70	70	70	70	0	271.0
71	71	71	71	71	0	263.0	71	71	71	71	71	0	271.0
72	72	72	72	72	0	263.0	72	72	72	72	72	0	271.0
73	73	73	73	73	0	263.0	73	73	73	73	73	0	271.0
74	74	74	74	74	0	263.0	74	74	74	74	74	0	271.0
75	75	75	75	75	0	263.0	75	75	75	75	75	0	271.0
76	76	76	76	76	0	263.0	76	76	76	76	76	0	271.0
77	77	77	77	77	0	263.0	77	77	77	77	77	0	271.0
78	78	78	78	78	0	263.0	78	78	78	78	78	0	271.0
79	79	79	79	79	0	263.0	79	79	79	79	79	0	271.0
80	80	80	80	80	0	263.0	80	80	80	80	80	0	271.0
81	81	81	81	81	0	263.0	81	81	81	81	81	0	271.0
82	82	82	82	82	0	263.0	82	82	82	82	82	0	271.0
83	83	83	83	83	0	263.0	83	83	83	83	83	0	271.0
84	84	84	84	84	0	263.0	84	84	84	84	84	0	271.0
85	85	85	85	85	0	263.0	85	85	85	85	85	0	271.0
86	86	86	86	86	0	263.0	86	86	86	86	86	0	271.0
87	87	87	87	87	0	263.0	87	87	87	87	87	0	271.0
88	88	88	88	88	0	263.0	88	88	88	88	88	0	271.0
89	89	89	89	89	0	263.0	89	89	89	89	89	0	271.0
90	90	90	90	90	0	263.0	90	90	90	90	90	0	271.0
91	91	91	91	91	0	263.0	91	91	91	91	91	0	271.0
92	92	92	92	92	0	263.0	92	92	92	92	92	0	271.0
93	93	93	93	93	0	263.0	93	93	93	93	93	0	271.0
94	94	94	94	94	0	263.0	94	94	94	94	94	0	271.0
95	95	95	95	95	0	263.0	95	95	95	95	95	0	271.0
96	96	96	96	96	0	263.0	96	96	96	96	96	0	271.0
97	97	97	97	97	0	263.0	97	97	97	97	97	0	271.0
98	98	98	98	98	0	263.0	98	98	98	98	98	0	271.0
99	99	99	99	99	0	263.0	99	99	99	99	99	0	271.0
100	100	100	100	100	0	263.0	100	100	100	100	100	0	271.0

PLAN	2	INPUT DATA FOR STATION	A4 ARE SAME AS FOR PLAN 1			
PLAN 2	INPUT DATA FOR STATION	CUMULATIVE AREA =	2.20	50	MI	
FEAR FLOW (CFS) 3697.	TIME (HR) 17.17	(CFS) (INCHES) (AC-FT)	6-HR 2092. 8.439 1037.	MAXIMUM AVERAGE FLOW 24-HR 616. 10.416 1227.	MAXIMUM AVERAGE STORAGE 24-HR 2. 2.	24.92-HR 593. 10.411 1222.
FEAR STORAGE (AC-FT) 11.	TIME (HR) 17.17		6-HR 6.			24.92-HR 2.
FEAR STAGE (FEET) 270.46	TIME (HR) 17.17		6-HR 268.53			24.92-HR 264.65

HYDROGRAPH AT STATION = 0.50
PLAN 2. A4

CA MON	HRHH	GRO	OUTFLOW	STORAGE	STAGE	DA	MON	HRHH	GRO	OUTFLOW	STORAGE	STAGE
0000	1	3	0.0	0.0	26.3	1	0020	101	25.0	0.0	26.3	0
0010	3	3	0.0	0.0	26.3	1	0025	102	29.0	0.0	26.3	0
0015	5	3	0.0	0.0	26.3	1	0030	103	31.0	0.0	26.3	0
0020	5	5	0.0	0.0	26.3	1	0035	104	34.0	0.0	26.3	0
0025	5	7	0.0	0.0	26.3	1	0040	105	36.0	0.0	26.3	0
0030	5	8	0.0	0.0	26.3	1	0045	106	42.0	0.0	26.3	0
0035	5	8	0.0	0.0	26.3	1	0050	107	46.0	0.0	26.3	0
0040	5	8	0.0	0.0	26.3	1	0055	108	50.0	0.0	26.3	0
0045	5	8	0.0	0.0	26.3	1	0059	109	54.0	0.0	26.3	0
0050	5	8	0.0	0.0	26.3	1	0100	110	59.0	0.0	26.3	0
0055	5	8	0.0	0.0	26.3	1	0105	111	64.0	0.0	26.3	0
0100	5	11	0.0	0.0	26.3	1	0110	112	69.0	0.0	26.3	0
0105	5	11	0.0	0.0	26.3	1	0115	113	73.0	0.0	26.3	0
0110	5	11	0.0	0.0	26.3	1	0120	114	78.0	0.0	26.3	0
0115	5	11	0.0	0.0	26.3	1	0125	115	82.0	0.0	26.3	0
0120	5	11	0.0	0.0	26.3	1	0130	116	87.0	0.0	26.3	0
0125	5	11	0.0	0.0	26.3	1	0135	117	91.0	0.0	26.3	0
0130	5	11	0.0	0.0	26.3	1	0140	118	95.0	0.0	26.3	0
0135	5	11	0.0	0.0	26.3	1	0145	119	103.0	0.0	26.3	0
0140	5	11	0.0	0.0	26.3	1	0150	120	110.0	0.0	26.3	0
0145	5	11	0.0	0.0	26.3	1	0155	121	111.0	0.0	26.3	0
0150	5	11	0.0	0.0	26.3	1	0200	122	111.0	0.0	26.3	0
0155	5	11	0.0	0.0	26.3	1	0205	123	111.0	0.0	26.3	0

1	0730	91	13.	0.1	263.1	1	1550	191	1834.	5.5	268.3	*	2	0010	291	22.	0.5	263.5
1	0735	92	14.	0.1	263.1	1	1555	192	1925.	5.7	268.5	*	2	0015	292	23.	0.5	263.5
1	0740	93	14.	0.1	263.1	1	1600	193	2029.	5.7	268.6	*	2	0020	293	24.	0.5	263.5
1	0745	94	16.	0.1	263.1	1	1605	194	2146.	6.0	268.7	*	2	0025	294	25.	0.5	263.5
1	0750	95	16.	0.1	263.1	1	1610	195	2270.	6.2	268.8	*	2	0030	295	26.	0.5	263.5
1	0755	96	17.	0.1	263.1	1	1615	197	2411.	6.5	268.9	*	2	0035	296	27.	0.5	263.5
1	0800	97	18.	0.1	263.1	1	1620	197	2533.	6.5	269.0	*	2	0040	297	28.	0.5	263.5
1	0805	98	21.	0.2	263.2	1	1625	198	2653.	7.6	269.1	*	2	0045	298	29.	0.4	263.4
1	0810	99	21.	0.2	263.2	1	1630	199	2853.	8.2	269.2	*	2	0050	299	30.	0.4	263.4
1	0815	100	23.	0.2	263.2	1	1635	200	3005.	8.8	270.0	*	2	0055	300	50.	0.4	263.4

PEAK FLOW
 (CFS)
 3492.
 TIME
 (HR)
 17.17
 (INCHES)
 6.202
 (AC-FT)
 10721
 1258.
 MAXIMUM AVERAGE FLOW
 24-HR
 611.
 10722
 1258.
 24.92-HR
 611.
 10722
 1258.
 PEAK STAGE
 (AC-FT)
 11.
 TIME
 (HR)
 17.17
 MAXIMUM AVERAGE STORAGE
 24-HR
 2.
 24.92-HR
 2.
 PEAK STAGE
 (FEET)
 270.46
 TIME
 (HR)
 17.17
 MAXIMUM AVERAGE STAGE
 24-HR
 264.95
 24.92-HR
 264.88
 24.92-HR
 264.88
 CUMULATIVE AREA = 2.20 SQ MI

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO 1 0.10	RATIOS C.25	APPLIED TO FLOWS RATIO 2 0.50
HYDROGRAPH AT	A1	2.20	1	FLOW	1752.	3505.
				TIME	17.00	17.00
	2	FLOW	1752.	3505.		
		TIME	17.00	17.00		
ROUTED TO	A2	2.20	1	FLOW	1750.	3501.
				TIME	17.00	17.08
	2	FLOW	1750.	4139.		
		TIME	15.33	14.00		
ROUTED TO	A3	2.20	**	PEAK	**	259.20
				STAGES IN FEET	204.54	17.08
	1	STAGE	287.90	13.94		
		TIME	15.26	3500.		
ROUTED TO	A3	2.20	1	FLOW	1749.	17.08
				TIME	17.04	3716.
	2	FLOW	3651.	14.00		
		TIME	15.33			
ROUTED TO	A4	2.20	**	PEAK	**	276.53
				STAGES IN FEET	275.26	17.08
	1	STAGE	276.42	14.00		
		TIME	15.33			
ROUTED TO	A4	2.20	1	FLOW	1749.	17.17
				TIME	17.04	3497.
	2	FLOW	3420.	17.17		
		TIME	15.42	3492.		
ROUTED TO	A4	2.20	**	PEAK	**	270.48
				STAGES IN FEET	268.13	17.17
	1	STAGE	270.34	17.17		
		TIME	15.42	270.48		

SUMMARY OF DAM DRAINAGE/BREACH ANALYSIS FOR STATION A2

PLAN 1

RATIO OF PNE	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.10	287.63	285.00	285.00	287.90	17.25	0.0
0.50	288.54	38.0	38.0	58.0	4.25	0.0
0.50	289.20	0.0	0.0	71.0	6.53	0.0

PLAN 2

	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 287.00 38. 0.	SPILLWAY CREST 285.38 0.	TOP OF DAM 287.90 56. 711.	
RATIO OF PHF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION (OVER TOP HOURS)
0.10	287.83	0.0	57.	686.	0.0
0.25	287.90	0.00	58.	5469.	0.11
0.50	287.91	0.01	58.	5563.	0.03
					TIME OF FALLURE HOURS
					17.25
					15.35
					13.92

*** NORMAL END OF JOB ***

AD-A103 935

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON --ETC F/6 13/13
NATIONAL DAM SAFETY PROGRAM, MAPLE LAKE DAM (NJ 00776), PASSAIC--ETC(U)
JUL 81 W GUINAN

DACW61-79-C-0011

DAEN/NAP-53842/NJ00776-81/ NL

UNCLASSIFIED

2 OF 2

AD-A
103 935



END
DATE
FILMED
10-81
DTIC

APPENDIX 6

REFERENCES

MAPLE LAKE DAM

APPENDIX 6
REFERENCES

MAPLE LAKE DAM

Chow, Ven Te, Open Channel Hydraulics, McGraw Hill Book Company, New York, 1959.

King, H.W. and E.F. Brater, Handbook of Hydraulics, McGraw Hill Book Company, New York, Fifth Edition 1963.

Lewis, J.V. and H.B. Kummel (1910-1912) Geologic Map of New Jersey, revised by H.B. Kummel, 1931, and by M.E. Johnson, 1950. New Jersey Department of Conservation of Economic Development Atlas.

Salisbury, Kummel, Peet and Whitson, (1902) Glacial Map of New Jersey.

Schway, G.O., R.K. Frevert, T.W. Edmister, and K.K. Barnes, Soil and Water Conservation Engineering, The Ferguson Foundation Agricultural Engineering Series, John Wiley and Sons, Inc., New York, 1966, 683 pp.

U.S. Army Corps of Engineers, Hydrologic Engineering Center, Flood Hydrograph Package (HEC-1) Users Manual-Preliminary, Davis, California, March 1981.

U.S. Department of Agriculture, Soil Conservation Service, Urban Hydrology for Small Watersheds, Technical Release No. 55, Washington, 1975.

U.S. Department of Commerce, Weather Bureau, "Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours", Hydrometeorological Report No. 33, Washington, 1977, 816 pp.

United States Department of Interior, Bureau of Reclamation, Design of Small Dams, U.S. Government Printing Office, Washington, 1977, 816 pp.

U.S. Department of Interior, Geological Survey, 7.5-Minute Series (topographic) maps, scale 1:24000, Contour Interval 10 feet: Paterson, New Jersey, (1955), Photorevised 1970.

Viessman, Warren, Jr., J.W. Knapp, G.L. Lewis, T.E. Harbaugh, Introduction to Hydrology, Harper and Row, Publishers, New York, Second Edition 1977, 704 pp.

EN
DATE
FILME